



DOCUMENT CONTROL

@ Copyright 2019

Edison Environmental & Engineering Pty Ltd

ABN 83 605 328 587

PO Box 564

Balmain NSW

admin@edisonenvironmental.com.au

This report is prepared solely for the use of the Client to whom this report is addressed and must not be reproduced in whole or part or included in any other document without our express permission in writing. No responsibility or liability to any third party is accepted for any damages arising out of the use of this report by any third party.

Report Title:	Preliminary Geotechnical Investigation Report: Proposed Master Plan Development, Barton Park, Bestic Street, Banksia New South Wales.				
Doc. Ref:	E17011-CU-15-R				
Client:	Prepared for MODE Design Corp Pty Lt	rd			
	Prepared By: Authorised By:				
Signature:	S.me	WW			
	Stephen McCormack, Principal Geotechnical Engineer B.E. (Civil) — CPEng, MIEAust, NER (geotechnical)	Dr Michael Petrozzi, Managing Director			

Revision Status:

Rev No.	Status	Date	Writer	Reviewer
0	Final	11 Sept 2020	SMC	M. Petrozzi

Documents Distribution (This Revision):

No of Copies	Туре	Recipient	Positions and Company
		Name	
1	E: twilliams@modedesign.com.au	Mr Tim Williams	Senior Landscape Architect MODE Design Corp Pty Ltd
1			



Preliminary Geotechnical Investigation Report: Proposed Master Plan Development Barton Park, Bestic Street, Banksia New South Wales.

Report ID: E17011-CU-15-R. Prepared for MODE Design Corp Pty Ltd.

TABLE OF CONTENTS INTRODUCTION 1. 8 **OBJECTIVE AND SCOPE OF WORK** 2. 9 3. SITE INFORMATION 10 3.1 SITE IDENTIFICATION 10 3.2 SITE DESCRIPTION 10 3.3 SITE HISTORY / BACKGROUND INFORMATION 10 3.4 **TOPOGRAPHY** 10 3.5 REGIONAL GEOLOGY AND SOILS 11 3.6 HYDROGEOLOGY 11 3.7 **3ACID SULFATE SOILS** 12 3.8 PREVIOUS GEOTECHNICAL INVESTIGATIONS 12 **METHODS OF INVESTIGATION** 13 4.1 BOREHOLE DRILLING OPERATIONS AND LOGGING 13 4.2 SOIL SAMPLING 15 4.3 IN-SITU PERMEABILITY TESTING 16 5. **INVESTIGATION RESULTS** 17 5.1 SUBSURFACE CONDITIONS 17 5.1.1 GROUNDWATER 17 PERMEABILITY AND WATER INFILTRATION ASSESSMENT 18 19 5.3 LABORATORY TESTING 5.3.1 SOIL SALINITY TESTING 20 5.3.2 AGGRESSIVITY TESTING 20 5.3.3 CALIFORNIAN BEARING RATION (CBR) TESTING 21 5.3.4 **ROCK STRENGTH TESTING** 22 DISCUSSION 6. 23 6.1 **GEOTECHNICAL ISSUES** 23 6.2 23 SITE PREPARATION 6.3 PAVEMENT SUBGRADE PREPARATIONS AND DESIGN 23 6.4 **FOUNDATIONS** 24 6.4.1 TIERED SEATING AREA AND AMENITIES BUILDING 24 25 6.4.2 MINOR STRUCTURES 6.4.3 AGGRESSIVITY / EXPOSURE POTENTIAL 25 6.5 EARTHQUAKE DESIGN 25 25 6.6 SALINITY 6.7 STORMWATER INFILTRATION 25 7. **CONCLUSION AND RECOMMENDATIONS** 26 8. **GENERAL LIMITATIONS** 27 9. **REFERENCES** 28



List of Figures

Figure 1: Site location Map

Figure 2: Site Plan

Figure 3: Location of the Boreholes (Aerial)
Figure 4: Location of the Boreholes (Survey)

List of Tables

Table 1: Summary of the Borehole Information

Table 2: Summary of Subsurface Conditions / Geological Model

Table 3: Electrical Conductivity Results

Table 4: Exposure classification (aggressivity) test results

Table 5: CBR Test Results

Table 6: Preliminary Foundation Design Parameters

List of Annexures

Annexure 1: Survey and Masterplan of the Proposed Development

Annexure 2: Previous Borehole Logs and Site Plan

Annexure 3: Registered Groundwater Bores within 200 m of Barton Park Boundary

Annexure 4: Edison Geotechnical Borehole Logs Annexure 5: Laboratory Certificates of Analysis



List of Abbreviations Units of Measure

% per cent

ug L⁻¹ Micrograms per Litre

ug m⁻³ Micrograms per Cubic Metre

ha Hectare km Kilometres m Metre

m AHD Metres Above Australian Height Datum

m BGL Metres Below Ground Level
m BTOC Metres Below Top of Casing
mg kg⁻¹ Milligrams per Kilogram
mg L⁻¹ Milligrams per Litre

mg m⁻³ Milligrams per Cubic Metre

mm Millimetre
ppm Parts Per Million
ppb Parts Per Billion

General

ABC Added Background Concentrations

ACL Added Contaminant Limit

ACM Asbestos Containing Materials

ADWG Australian Drinking Water Guideline

AEC Areas of Environmental Concern

AF Asbestos Fines

AGST Above Ground Storage Tank
AHD Australian Height Datum

ALS Australian Laboratory Services Pty Ltd

ANZECC Australian and New Zealand Environment and Conservation Council

APHA American Public Health Association

ASS Acid Sulphate Soils

ASSMAC Acid Sulfate Soils Management Advisory Committee

BGL Below Ground Level

BOD Biochemical Oxygen Demand

BTEX Benzene, Toluene, Ethylbenzene and Total Xylenes
CLM Act NSW Contaminated Land Management Act, 1997
CMPC Conceptual Model of Potential Contamination

COC Chain of Custody

CoPC Contaminants of Potential Concern

CSM Conceptual Site Model
CT Contaminant Threshold
DA Development Application
DAC Data Acceptance Criteria
DCP Development Control Plan

DNAPL Dense Non-Aqueous Phase Liquid

DP Deposited Plan

DQI Data Quality Indicator
DQO Data Quality Objectives
DSI Detailed Site Investigation



EIL Ecological Investigation Levels
EMP Environmental Management Plan

EOH End of Hole

EPA Environment Protection Authority

EPA Act Environmental Planning and Assessment Act, 1979

EQL Environmental Quantitation Limit ESA Environmental Site Assessment ESL Ecological Screening Level

FA Fibrous Asbestos

FID Flame Ionisation Detector

GIL Groundwater Investigation Level

GPS Global Positioning System

HIL Health Based Investigation Levels

HSL Health Screening Levels
IAA Interim Audit Advice
LCS Laboratory Control Sample
LEP Local Environment Plan

LFG Landfill Gas

LNAPL Light Non-Aqueous Phase Liquid

LOR Limit of Reporting

MDS Multi-Dimensional Scaling

NATA National Association of Testing Authorities

ML Management Limits

NATA National Association of Testing Authorities

ND Not Detected

NEPC National Environmental Protection Council
NEHF National Environmental Health Forum
NEPM National Environment Protection Measure
NHMRC National Health and Medical Research Council

NL Not Limiting
NSW New South Wales

OCP Organochlorine Pesticides

OEH Office of Environment and Heritage
OPP Organophosphorous Pesticides
PAH Polycyclic Aromatic Hydrocarbons

PCB Polychlorinated Biphenyls
PID Photo-ionisation Detector

POEO Act Protection of the Environment (Operations) Act, 1997

PQL Practical Quantitation Limit
PSI Preliminary Site Investigation
PSH Phase Separated Hydrocarbon

PSP Project Safety Plan

QA/QC Quality Assurance and Quality Control

RL Reduced Level

RPD Relative Percentage Difference
RSL Regional Screening Level
SAC Site Assessment Criteria

SAQP Sampling, Analysis and Quality Plan

SAR Site Audit Report SAS Site Audit Statement



SCC Specific Contaminant Concentration

SCEW Standing Council on Environment and Water

SILs Soil Investigation Levels

SPOCAS Suspension Peroxide Oxidation – Combined Acidity and Sulfate

SPT Standard Penetration Test

SVOC Semi-Volatile Organic Compounds

SWL Standing Water Level

TCLP Toxicity Characteristics Leaching Procedure

TD Termination Depth
TDS Total Dissolved Solids

TPH Total Petroleum Hydrocarbons
TRH Total Recoverable Hydrocarbons

TV Trigger Value

USEPA United States Environment Protection Agency

UST Underground Storage Tank
VOC Volatile Organic Compounds

VOCCs Volatile Organic Chlorinated Compounds

WHS Work Health and Safety

-- On tables is 'not calculated', 'not measured', 'no criteria' or 'not applicable'



Preliminary Geotechnical Investigation Report: Proposed Master Plan Development Barton Park, Bestic Street, Banksia New South Wales.

Report ID: E17011-CU-15-R. Prepared for MODE Design Corp Pty Ltd.

1. Introduction

Bayside Council (Council) is the manager of the open space referred to as Barton Park as shown on Figures 1 and 2. In its' role as manager of Barton Park, Council has developed a Master Plan for the southern portion of the site (the site) (consisting of the following elements (Figures 3 and 4):

- Demolition of the existing grandstand and associated buildings;
- Construction of a new sporting amenities building, including public amenities, change rooms, canteen and storage;
- Construction of a new tiered seating area suitable for a minimum of 400 people with shade structure;
- Construction of four (4) turf playing fields;
- Construction of four (4) multi-purpose synthetic courts and supporting infrastructure;
- Off leash dog area;
- Playground or natural play area;
- Carparking and vehicular access driveways;
- Improvements to the public domain, including footpaths, paving, landscaping and street furniture;
- Shared pathway/cycleway;
- Passive recreation opportunities including lookouts, picnic areas, seating and fitness.

MODE Design Corp Pty Ltd (MODE) has been engaged by Council to undertake design works necessary to implement the masterplan. Edison Environmental & Engineering Pty Ltd (Edison) has been commissioned by MODE to undertake a complete a preliminary geotechnical investigation at the site to support the Masterplan development.

A site survey and the proposed masterplan are provided for reference in Annexure 1. It is understood that the new facilities will be constructed at (or near) existing grade and that preliminary geotechnical investigation is required to assist with the preliminary design of the development.

The report presents the factual results of all the field investigations completed by Edison to date and provides interpretation and recommendations regarding the ground conditions at the site in accordance with client requirements and the agreed scope of work.

It is assumed that each of the structures listed above will be constructed at (or near) existing grade to minimise future earthworks. With respect to the proposed grassed fields, it is assumed that they will be prepared in a manner consistent with the existing fields, including being top-dressed as required to manage future undulations.



2. Objective and Scope of Work

The objective of this investigation is to provide a preliminary characterisation of geotechnical conditions at the site for use in project design.

The scope of work is as follows:

- Visual appraisal of the site conditions and locality;
- Review of geological, soils and acid sulfate soil maps;
- Drilling and logging of boreholes to compliment the data collected in past environmental investigations as summarised by Edison (2020);
- Perform Standard Penetrometer Tests (SPTs) the boreholes to assess the consistency and/or relative density of the soil profile;
- Collection of representative soil samples for geotechnical testing;
- Analysis of selective samples for assessment of soil salinity and aggressivity;
- Collection of representative samples of bedrock;
- Strength testing of the bedrock samples;
- The performance of soil permeability and infiltration tests to determine the soil infiltration rate and coefficient of permeability to assist with the design of a potential stormwater absorption system; and
- Engineering assessment and reporting.

In preparing this report it is assumed that structures listed in Section 1 will be constructed at (or near) existing grade to minimise future earthworks. With respect to the proposed grassed fields, it is assumed that these will be prepared in a manner consistent with the existing fields, including being top-dressed as required to manage future undulations.



3. Site Information

3.1 Site Identification

The site is bounded by Muddy Creek to the east, Bestic Street to the south, the Spring Street drain to the north and a combination of low-density residential properties and the Arncliffe Market gardens to the west (Refer to a Figure 1). The site covers an area of approximately 19 hectares and encompasses the following allotments:

- Part of CP 12437-3000 (south of Spring Street Drain);
- Part of Lot 1 DP 576148 (south of Spring Street Drain);
- Part of Lot 100 DP 1133869;
- Part of Lot 1 DP 514811.
- Part of Lot 7303 DP 1148740 (south of Spring Street Drain);
- Part of land referred to in CP 7979-3000.

The site is zoned for recreation/open-space land use and Special Uses (F6 Corridor) under Sydney Regional Environmental Plan 33 - Cooks Cove (2004 No 397).

3.2 Site Description

Most of the site is covered by grass and used as a park with three soccer playing fields. Structures on the site consist of brick soccer club and amenities buildings constructed on a concrete slab. There is also the former St George stadium which has been partly demolished by removing the roof sheets, glazing and doors. Access to all buildings are secured by locked doors and/or fencing.

The site is a former landfill. The waste mass covers most of the site with batters sloping towards each site boundary. Except for the former, disused St George Soccer Stadium which is understood to have been constructed on a raised fill mound on the former landfill, the surface of the former landfill mound is grassed and used for passive recreation. The site is uneven due to differential settlement of the underlying waste material. Batters of the former landfill mound are grassed (southern portion) or vegetated with shrubs (northern portion). The Landing Light Wetland is in the north-west portion of the site. The wetland is tidal and relates to Spring Street Canal by a concrete pipe. The level of the pipe allows shallow water depth to be retained within the wetland at low tide.

3.3 Site History / Background Information

It is understood that the site was used as a market garden until early in the twentieth century (Maunsell, 2001; Edison, 2020). Parts of the site were then used as a sewage farm serving south and western Sydney for approximately 40 years commencing in the late nineteenth Century. The sewage farm was decommissioned in the 1940s and filled with waste by Rockdale Council. Following completion of landfill operations (1940s-1980s), the site was covered with soil, grassed and converted into a series of sports fields.

Since 2001 the site has been the subject of a series of proposals seeking consent to redevelop the site as a golf course. No substantial changes have been made to the site since 2001 other than the closure of the St George soccer stadium.

3.4 Topography

The park and playing fields are relatively flat and according to the survey plan (Annexure 1), the surface elevation is between approximately 3.5m and 4.5m above Australian Height Datum (AHD). As previously



mentioned, the park and playing fields are part of the former landfill with batters sloping down towards the boundaries where the surface elevation is between approximately 0.5m and 1.0m AHD.

3.5 Regional Geology and Soils

The Sydney 1:100,000 Geological Series Map describes the underlying natural lithology as consisting of silty to peaty quartz sand, silt and clay with ferruginous and humic cementation in places and common shell layers. This material is most likely to be of alluvial origin, deposited as sub-aerial and sub-aqueous component of the Cooks River delta. The natural deposit has been reworked significantly in the last century as part of river diversion works. These works would have involved significant dredging operations (CES, 2001a). Additionally, waste landfills have been constructed over the natural sediments (Figure 2).

Based on borehole logs from past studies presented in Annexure 2, the generalised stratigraphic sequence for the site is as follows:

- Cover soil over waste (former landfill areas): Silty sand to sandy cover soil ranging from 0.1 to 2.7 m thickness over waste material;
- Waste (mounds) consisting of compacted municipal waste material including rubber, cloth, wood, glass, plastic, metal, fabric, ceramic, ash, construction/demolition waste and organic matter;
- Areas to the periphery of the waste mounds are underlain by reworked alluvial sediments associated with historical diversions/re-alignments of the Cooks River/Muddy Creek with surface fill material;
- Natural alluvial/estuarine sediments consisting of fine to medium-grained, loose sands to coarsegrained dense sands, black/brown peat and soft to dense clays;
- Sandstone bedrock.

3.6 Hydrogeology

Groundwater associated with filled land and underlying unconsolidated sediments is unconfined. The regional direction of groundwater flow is towards the Cooks River (CES, 2017b). Spring Street wetland, Spring Street Drain and the Landing Light Wetland are local groundwater sinks along with the Cooks River and Muddy Creek.

A list of registered groundwater extraction bores within 200 m of the site boundary bores is provided in Annexure 3 along with a plan showing their locations. Notably, there are no registered groundwater extraction bores on the site (GW111316 is a monitoring bore). A site inspection by Edison and enquiries with Bayside Council did not identify any unregistered extraction bores on the site. There are five (5) registered groundwater bores on residential properties to the west (hydraulically upgradient) of the site and four (4) bores to the south-east on the opposite side of Muddy Creek.

Groundwater at the site is unconfined, occurring within the waste mass and underlying alluvium Edison (2020). Groundwater is impacted with constituents derived from anoxic and anaerobic waste degradation (primarily ammonia) and is hydraulically connected to the surrounding surface-water bodies resources, namely: Spring Street Wetland; Spring Street Drain/Canal; Cooks River; Muddy Creek and the Landing Lights/Riverine Park Wetlands. The estimated quantity of impacted groundwater (and therefore contaminant loading) discharging to surface-water bodies is small relative to the volume of the diurnal tidal prism. Furthermore, the receiving waterways are substantially degraded as a result of urban runoff and organic-rich bed sediments, particularly in the wetlands, which are also likely to constitute a source of ammonia at low tide. On these bases, the risks arising from ammonia-impacted groundwater to baseflows



in surface-water bodies are considered to be low. The likelihood of potential human contact with impacted groundwater is low due to the configuration of the discharge zone to receiving surface-water resources.

Groundwater flow contours prepared by CES (2016a) are presented in Annexure 3. Indicating a radial groundwater flow pattern which is a subdued reflection of the surface topography.

3.7 3Acid Sulfate Soils

Based on the results of SPOCAS testing (CES, 2008a), the natural sediments are classified as Potential Acid Sulfate Soils (PASS). PASS are soils containing iron sulfides or sulfidic material (usually ferrous iron disulfide or pyrite) which are waterlogged soils, rich in pyrite, that have not been exposed to air and oxidised. Any disturbance that admits oxygen (such as excavation works) will lead to the development of actual acid sulfate soil layers, which may pose an environmental risk. An Acid Sulfate Soils Management Plan (ASSMP) would be required in the event that works involving the disturbance of natural sediments are proposed.

3.8 Previous Geotechnical Investigations

Edison is not aware of any previous geotechnical investigations having been completed at the site. However, there have been a number of environmental studies completed at the site as summarised by Edison (2020) as part of previous planning proposals that relate to the site and public land extending north to the Kogarah Golf Course. This land has been variously referred to as Cooks Cove, Cook Cove and Cooks Cove Inlet and is herein referred to as the "Cooks Cove Project".

These investigations included the drilling of numerous boreholes across the site. A copy of the available borehole logs is provided for reference in Annexure 2 along with plans showing the borehole locations. A summary of the borehole information, including total depth, depth of fill and depth to bedrock (where available), is provided in Table 1 along with boreholes drilled as part of this investigation.

With the exception of boreholes D1G01 and D1G02, all the boreholes were relatively shallow and did not reach the bedrock. Both D1G01 and D1G02 were deeper bores which extended into the bedrock formation which was encountered at a depth of between 17.7m and 20.8m below ground surface (bgs). The bedrock formation was predominately sandstone and based on the positioning of the boreholes, the bedrock appeared to be dipping down towards the north-east.

As indicated above, the majority of the boreholes encountered fill comprising significant proportions of waste which supports the history of landfilling at the site. The extent of past landfilling is indicated on Figure 2.

Information from these past borehole logs as summarised in Table 1 has been used in the development a geological model for the site which is presented in a subsequent section of this report.



4. Methods of Investigation

Fieldwork was completed in August 2020 and comprised the following activities:

- Drilling and logging of one (1) borehole (BHDG101) within the approximately footprint of the proposed tiered seating area and amenities building to provide a preliminary assessment of the fill/soil conditions and the depth to bedrock at this location (Figures 3 and 4);
- Performance of Standard Penetration Tests (SPTs) in borehole BHDG101 to assess the consistency and/or relative density of the soil profile;
- Drilling and logging of four boreholes (BHDG102 to BHDG105) within the approximately footprint of the proposed new artificial grass fields to complement the existing information and to provide an additional assessment of the shallow fill/soil conditions (Figures 3 and 4);
- Collection of representative soil samples at regular intervals from the boreholes for selective laboratory testing;
- Collection of rock core from the borehole BHDG101 for selective laboratory testing; and
- Performance of *in-situ* soil permeability and infiltration tests to determine the soil infiltration rate and the coefficient of permeability.

4.1 Borehole Drilling Operations and Logging

A scan for potential underground services and utilities was completed on behalf of MODE by Suresearch Pty Ltd. Prior to commencement of the drilling operations, the report and ground markings by Suresearch were cross checked with the results of a Dial Before you Dig (DBYD) search conducted by Edison.

Boreholes were drilled using an Hanjin D&B 8D track-mounted, hydraulic drill rig operated by Geosense Drilling Pty Ltd. Bore holes were advanced ad using a combination of Solid Flight Augers (SFA) through fill, wash boring through underlying alluvium and NMLC diamond coring for bedrock. Borehole BHDG101 was advanced through the fill/landfill layer and the underlying alluvial soil profile before terminating within the underlying bedrock formation. The remaining bores (BHDG102 to BHDG105) were terminated at 3m depth in the waste landfill layer and were primarily used to better assess the depth of landfill cover soils placed over waste in addition to provide an indication as to the consistency of waste fill.

SPT tests were performed at regular intervals in borehole BHDG101 in accordance with *Australian Standard Test Method* AS1289.6.3.1-1997.

A summary of the subsurface conditions encountered is provided in Section 5.1, while a summary of the borehole information, including total depth, depth of fill and depth to bedrock, is provided in Table 1. The locations of the boreholes are shown on Figure 3 along with a recent aerial photograph and Figure 4 also shows the proposed masterplan.



Table 1: Summary of the Borehole Information

Borehole ID	Date Completed	Drilling Method	Total Depth	Depth of Filling	Depth Bedrock	to	Groundwater Well Screen Interval
			(m BGS)	(m BGS)	(m BGS)		(m BGS)
Edison 2020 B	Boreholes						
BHDG101	17-Aug-20	SFA/WB/Core	19.43	9.5 *	16.2		
BHDG102	17-Aug-20	SFA	3.0	≥3.0 *	ND		
BHDG103	17-Aug-20	SFA	3.0	≥3.0 *	ND		
BHDG104	17-Aug-20	SFA	3.0	≥3.0 *	ND		
BHDG105	17-Aug-20	SFA	3.0	≥3.0 *	ND		
Available Bore	eholes From Prev	vious Environmental	Studies (Refer t	o Annexure 2)			
DBH801	13-May-08	PT	2.4	1.7	ND		
DBH802	13-May-08	PT	1.2	0.8	ND		
DBH803	15-May-08	НА	0.35	≥0.35	ND		
DBH804	13-May-08	PT	1.2	≥1.2 *	ND		
DBH805	10-Apr-08	SFA	1.2	≥1.2 *	ND		
DBH806	04-Apr-08	SFA	1.5	≥1.5 *	ND		
DBH807	04-Apr-08	SFA	1.5	≥1.5 *	ND		
DBH808	04-Apr-08	SFA	1.0	≥1.0 *	ND		
DBH809	10-May-08	SFA	1.2	≥1.2 *	ND		
DBH810	13-May-08	PT	1.2	0.7	ND		
DBH811	04-Apr-08	SFA	1.2	≥1.2 *	ND		
DBH812	04-Apr-08	SFA	1.0	≥1.0 *	ND		
DBH813	01-Apr-08	SFA	1.1	≥1.1 *	ND		
DBH814	04-Apr-08	SFA	1.0	≥1.0 *	ND		
DBH815	01-Apr-08	SFA	1.5	≥1.5 *	ND		
DBH816	01-Apr-08	SFA	2.0	≥2.0 *	ND		
DBH817	07-Apr-08	SFA	1.5	0.5	ND		
DBH818	04-Apr-08	SFA	1.0	≥1.0 *	ND		
DBH819	07-Apr-08	SFA	1.5	≥1.5 *	ND		
DBH820	07-Apr-08	SFA	1.5	0.5	ND		
DBH821	07-Apr-08	SFA	1.5	≥1.5 *	ND		
DMW803A	10-Apr-08	PT	3.6	1.1 *	ND		0.6 - 3.6
DMW805	01-Apr-08	SFA	5.0	≥5.0 *	ND		0.9 - 3.9
DMW806A	07-Apr-08	SFA	3.5	1.5	ND		0.5 – 3.5
D1MW1	19-Oct-15	SFA	6.0	3.3 *	ND		1.0 – 5.5
D1MW2	20-Oct-15	SFA	5.5	3.6 *	ND		1.0 – 5.5
D1MW3	19-Oct-15	SFA	7.0	5.5 *	ND		2.0 – 7.0
D1MW4	19-Oct-15	SFA	6.0	≥6.0 *	ND		1.0 – 5.0
D1MW5	15-Oct-15	SFA	7.3	≥7.3 *	ND		2.2 – 7.2
D1MW5b	15-Oct-15	SFA	2.2	≥2.2 *	ND		
D1MW6	15-Oct-15	SFA	7.0	≥7.0 *	ND		
D1MW7	16-Oct-15	SFA	4.0	≥4.0 *	ND		0.5 - 4.0
D1MW8	16-Oct-15	SFA	4.0	≥4.0 *	ND		0.5 - 4.0
D1G01	22-Oct-15	ADV/Core	28.26	6.2 *	20.8		2.0 – 6.0



D1G02	21-Oct-15	ADV/Core	19.96	7.5 *	17.7	2.0 - 6.0
D1BH10	16-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH11	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH12	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH13	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH14	12-Oct-15	SFA	2.4	≥2.4 *	ND	
D1BH15	12-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH16	12-Oct-15	SFA	2.2	≥2.2 *	ND	
D1BH17	12-Oct-15	SFA	1.0	≥1.0 *	ND	
D1BH18	12-Oct-15	SFA	1.1	≥1.1 *	ND	
D1BH19	12-Oct-15	SFA	2.0	≥2.0 *	ND	
D1BH20	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH21	12-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH22	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH23	16-Oct-15	SFA	3.0	2.2 *	ND	
D1BH24	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH25	14-Oct-15	SFA	3.0	1.8 *	ND	
D1BH26	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH27	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH28	16-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH29	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH30	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH31	14-Oct-15	SFA	3.0	2.2 *	ND	
D1BH32	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH33	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH34	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH36	13-Oct-15	SFA	2.3	≥2.3 *	ND	
D1BH37	16-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH39	13-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH41	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH42	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH43	14-Oct-15	SFA	3.0	≥3.0 *	ND	
D1BH44	14-Oct-15	SFA	0.9	≥0.9 *	ND	
D1BH45	14-Oct-15	SFA	3.0	≥3.0 *	ND	
m PCC = motro	s holow ground surf	260				

m BGS = metres below ground surface

ND – Not Determined

HA – Hand Auger

SFA – Solid Flight Auger

WB - Wash Boring

ADV – Casing Advancing

Core – Diamond coring of bedrock

4.2 Soil Sampling

Geotechnical soil and/or rock samples were collected from regular intervals from each borehole and submitted to either Eurofins MGT laboratory (Eurofins), Macquarie Geotechnical or MHK Geotechnical Pty Ltd for testing.

^{*} filling included landfill waste material



4.3 In-Situ Permeability Testing

An *in-situ* permeability test was conducted to assess the hydraulic conductivity of the near-surface fill/soils. This testing was undertaken to allow the infiltration rate to be estimated for the design of a potential future absorption system to manage stormwater from the new structures. The tests were undertaken approximately 10m to the north of borehole BHDG101 which is within close proximity to the proposed tiered seating and the amenities building. The results of the testing are provided below in Section 5.2.



5. Investigation Results

5.1 Subsurface Conditions

The generalised stratigraphic sequence (from top to bottom) is as follows:

- Cover soil (topsoil);
- General fill possibly being a capping layer predominately comprising silty sand and sand with minor construction waste;
- Waste fill comprising landfilled waste material;
- Natural alluvial/estuarine sediments consisting of fine to medium-grained, loose sands to coarse-grained dense sands, black/brown peat and soft to dense clays;
- Bedrock which predominately comprises sandstone.

More detailed descriptions of the subsurface conditions are provided below in Table 2 and in the borehole logs provided in Annexure 2 and Annexure 4.

5.1.1 Groundwater

Groundwater was encountered at approximately 4.5m bgs within borehole BHDG101. Groundwater was not encountered in the shallow (3 m deep) boreholes (BHDG102 to BHDG105). Previous borehole logs indicate that groundwater is unconfined (Edison, 2020) and occurs at depths of between 1.0m and 5.8m bgs.



Table 2: Summary of Subsurface Conditions / Geological Model

Layer / Unit	Description	Depth to Base of Layer (m)	Consistency / Relative Density ⁽¹⁾ / Rock Strength
1- TOPSOIL	SAND / Silty SAND: dark brown, fine to medium grained with roots	0.1 – 0.2	Loose
2 – GENERAL FILL	Silty SAND / SAND / Gravelly SAND: dark brown, grey and brown, fine to coarse grained sand, fine to coarse gravel with some cobble sizes and some construction and demolition waste (predominately brick and concrete).	1.0 – 1.7	Loose to medium dense
3 – WASTE FILL	Clayey SAND and SAND with much waste material (including wood, glass, plastic, metal, concrete, wire and rubber) and minor silt and gravel.	1.1 – 9.0	Very Loose
4 - NATURAL SOIL (Alluvial)	SAND / Silty SAND and CLAYEY SAND: light grey and dark grey, fine to medium grained sand, with shell fragments and pockets/bands or clay/organics. Noticeable landfill odour and a hydrocarbon odour was also noted in some areas.	13.5 - 18.5	Very Loose to Loose with some medium dense bands
5 – NATURAL SOIL (Residual)	Clayey SAND and Sandy CLAY: light grey, white and brown, fine to medium sand, low plasticity clay and trace gravel (sandstone).	16.2 - 20.8	Medium dense to dense / Stiff to Very Stiff
6a - BEDROCK	SANDSTONE with minor SHALE/LAMINITE bands: black, grey, orange, pink, fine to medium sandstone, extremely weathered to distinctly weathered (Class V shale/sandstone - Pells et al 2019)	17.4 - 24.85	Extremely low to low strength
6b - BEDROCK	SANDSTONE: grey and light grey, fine grained, fresh (Class III/II sandstone - Pells et al (2019)		Medium to high strength

Note 1: Determined from the borehole and SPT test observations

5.2 Permeability and Water Infiltration Assessment

In accordance with Rockdale Councils' 'Technical Specification: Stormwater Management' (RCC, 2011) on-site absorption is a suitable method of managing stormwater provided the base of the absorption system is at least 0.5m above bedrock and 1.0m above the water table. In this regard, on-site absorption is considered suitable, although the nominal rate of absorption must exceed 0.05 litres/second/m². Physical limitations are high water table, rock close to the surface or contaminated soils. Additionally, increasing infiltration has the potential to increase landfill leachate and landfill gas generation and should not be undertaken on this basis.

Notwithstanding this, Edison performed some *in-situ* variable (falling) head permeability tests to estimate an appropriate coefficient of permeability (k) and infiltration rate. The tests were conducted after saturating the test location for approximately 2 hours to provide a more conservative test result and mimic prolonged rainfall events.



The variable-head tests involved the use of a 235mm diameter cylinder (0.043 m²), secured in the ground using with excavated. The base of the cylinder was seated in fill comprising of compacted gravelly sand with some brick and concrete.

Markings on the cylinder indicating the height above the base of the cylinder were used to determine the piezometric head (Hc) of water above either the water table or any aquaclude (e.g. bedrock or permanent water table). In this case, the piezometric head was measured from the depth to groundwater at a nearby well which was 3.5 m bgl.

For the variable head tests, the cylinder was partially filled with water and the drop-in water head was recorded at regular intervals.

By applying the same Hvorslev (1949) variable head formula for a cylinder in a uniform soil which is flush with the base (Case C from Lambe and Whitman, 1969), the co-efficient of soil permeability (k) was determined. Using the calculated soil permeability rates, and assuming a piezometric head of 3.2 m, the infiltration rate was also determined. A piezometric head of 3.2 m equates to a water level which is approximately 0.3 m below ground, and this was adopted to mimic water within a submerged infiltration pit.

The results of each variable head test, and equivalent infiltration rate, is provided below:

	Test 1	Test 2
Soil permeability (k – cm/sec)	4.8 x 10 ⁻⁵	4.0 x 10 ⁻⁵
Infiltration Rate (L/m²/sec)	0.023	0.019

In-situ permeability tests were also carried out on the cover soils at two other locations as part of a previous environmental study (CES, 2008b) and the measured permeability ranged between 5.3×10^{-6} cm/sec at DBH811 to 1.7×10^{-3} cm/sec at DBH815. The results show that cover soils are of variable permeability which is attributed to the variability in composition and compaction.

Finally, the infiltrations rates measured as part of this investigation were below the minimum rate specified by Council for absorption systems to be considered suitable (RCC, 2011).

5.3 Laboratory Testing

Representative soil samples were selected for the following geotechnical testing parameters:

- Electrical Conductivity (EC) to provide an assessment of the salinity potential of the soil profile;
- Sulphate, Chloride, resistivity and pH to determine the exposure classification of the soil with respect to buried structural concrete and unprotected steel;
- Californian Bearing Ratio (CBR) testing to evaluate the mechanical strength of the upper soil profile to assist with future pavement design; and
- Point load strength index testing of the recovered bedrock core to characterise the strength of the bedrock.

The laboratory test results are presented in Annexure 5. A summary of the results is provided in the following sub-sections.



5.3.1 Soil Salinity Testing

Soil salinity was assessed with reference to guidance published by the Department Land and Water Conservation NSW (DLWC, 2002). Selected samples of natural soil were submitted to Envirolab for NATA accredited testing of Electrical Conductivity (EC), which is the primary indicator of salinity.

The raw EC results and the EC_e results (EC data multiplied by a conversion factor which depends upon the soil texture / type) are provided in Table 3.

Table 3: Electrical Conductivity Results

Sample ID	Sample Location / Depth	Sample Description	EC (dS/m)	Multiplication Factor ¹	EC _e (dS/m)
ZZ170820-01	BHDG101 / 1.5- 1.95m	FILL – Clayey SAND	0.18	14	2.52
ZZ170820-04	BHDG101 / 12.0 - 12.45m	FILL - Silty SAND	1.00	14	14.00
ZZ170820-05	BHDG101 / 13.5 - 13.95m	FILL - Silty SAND	0.58	14	7.00

According to the DLWC (2002), ECe results less than 2dS/m are considered to be non-saline, ECe results between 2dS/m to 4dS/m are slightly saline, ECe results between 4dS/m to 8dS/m are moderately saline, ECe results between 8dS/m to 16dS/m are very saline and results over 16dS/m are considered to be highly saline. The above test data indicate that the fill/natural soil profile is sightly to very saline.

5.3.2 Aggressivity Testing

Selected soil samples were submitted to Envirolab for NATA accredited testing of pH, sulfate, chloride and resistivity to provide a preliminary assessment of the exposure classification (or the aggressiveness/corrosiveness potential) of the soil with respect to future buried steel and/or concrete (e.g. footings).

To determine the aggressiveness of the soil and water environment on concrete or steel, chemical test results are compared to Table 6.4.2(C) and Table 6.5.2(C) from Section 6 of the Australian Standard AS 2159-2009 which specify criteria to assess the 'exposure classification' for a concrete or steel piles. The Standard has two classes of soil conditions:

- (A) high permeability soils below groundwater; and
- (B) low permeability soils and all soils above groundwater.

For this site, the soil samples are considered to be either condition 'A' or condition 'B' depending on if they were above or below the water table (i.e. sand below the water table – A or sand above the water table – B). Based on the chemical testing results, the standard provides a range of 'exposure classifications' from non-aggressive to very severe. For the range of chemical conditions in the soil surrounding the structure, the condition leading to the most severe aggressive conditions is adopted.

A summary of the soil results is provided in Table 4.



Table 4: Exposure classification (aggressivity) test results

Sample ID	Sample Location / Depth	Sample Description	Soil Condition	рН	Sulphate (SO ₄) mg/kg	Chloride (Cl) mg/kg	Resistivity Ohm.cm
ZZ170820-01	BHDG101 / 1.5-1.95m	FILL – Clayey SAND	В	7.3	81	36	5,600
ZZ170820-04	BHDG101 / 12.0 – 12.45m	FILL - Silty SAND	A	8.3	210	2000	21,000
ZZ170820-05	BHDG101 / 13.5 – 13.95m	FILL - Silty SAND	Α	8.4	150	1100	15,000

The aggressivity potential of an environment on concrete is dependent on the sulphate and pH levels of the soil. Based on the test results above and taking into account the 'worst-case' sample results, the subsurface profile is considered to be mildly aggressive towards concrete. However, the standard also states that concrete piles exposed to domestic waste refuse should be designed based on severe aggressivity. According to Australian Standard AS 3600-2009, specifically Table 4.8.1, a severe aggressivity rating equates to an exposure classification of 'B2'. This exposure classification is also suitable for the salinity levels in the fill and natural soil profile and for piles submerged in seawater.

The corrosive potential of an environment on unprotected steel is normally dependent on pH, chloride, and resistivity levels of the soil. Based on the limited number of test results above and considering the 'worst-case' sample results, the subsurface profile is considered to be non-aggressive / non-corrosive towards any unprotected steel. However, should any unprotected steel elements extend into the landfill material then a severe classification should be adopted. This classification is also appropriate for any unprotected steel submerged in seawater.

5.3.3 Californian Bearing Ration (CBR) Testing

To assist with the potential design of a flexible pavement for any future pavements, a bulk sample collected from boreholes BHDG103 and BHDG104/BHDG105 and tested for the CBR. To assist with calculation of the desired compaction for each CBR test, a dry density / optimum moisture content relationship test (otherwise referred to as a compaction test) was also completed on the same samples.

Bulk samples were collected from 0.2 m to 1.0 m depth representing the upper, predominately sandy fill layer. This layer was targeted because it is expected to remain in place as part of the Masterplan implementation and therefore this material will comprise the future pavement subgrade.

CBR samples were remoulded in the laboratory and compacted to approximately 98% Standard Maximum Dry Density (SMDD) at Optimum Moisture Content (OMC). Prior to testing the compacted samples were then soaked for 4 days under a surcharge load of 4.5 kg to provide soaked CBR values. Soaked CBR values are provided in **Table 5**, along with the optimum moisture content of each sample and the moisture content at compaction.



Table 5: CBR Test Results

Sample ID	Sample Location / Depth (m)	Sample Description	CBR Value (%)	Optimum Moisture	Maximum Dry Density
	•	• 1	5.0mm	Content (%)	(t/m³)
G3	BHDG103/0.2 – 1.2m	SAND with minor silt and gravel	40.0	14.1	1.769
G4/G5	BHDG104 & BHDG105/0.2 -1.0m	Gravelly SAND and SAND	35.0	11.9	1.87

It is noted that the CBR values presented in Table 5 are based on the basis that the subgrade material is compacted in the laboratory to approximately 100% standard compaction. However, this level of compaction (or a minimum of 95% standard compaction) is unlikely to be achieved in the field because of the poor quality of the underlying waste fill. Caution should therefore be applied in the use of the reported CBR values for conventional a conventional pavement design. Rather, Edison recommends that other engineering measures be used to reinforce the subgrade and, in turn, improve the lifespan of the pavements. Further discussion is provided below in Section 6.0.

5.3.4 Rock Strength Testing

Point-load index (I_{s50}) testing was undertaken on representative samples of rock core in order to assess the strength of the bedrock encountered at the site. Sub-sampling and testing were undertaken by MHK Geotechnical Pty Ltd on behalf of Edison.

Point load tests were conducted at approximately 1 m intervals, subject to the rock quality. Point load test values are routinely multiplied by a factor of 15 to 20 to estimate an Unconfined Compressive Strength (UCS) value of rock samples, although the correlation between point-load index and UCS values is known to vary significantly. For the purpose of this investigation a multiplication factor of 15 was adopted for estimating the UCS value from the point load tests.

For point load testing, rock core samples were loaded in the test apparatus and the failure load was recorded. Samples of the core were loaded diametrally and axially and the failure loads for each recorded. Results for core samples loaded axially ranged from 0.41 MPa to 1.33 MPa with an average of 0.92 MPa. Results for diametrally-loaded samples ranged from 0.50Pa to 1.11MPa with an average of 0.88MPa. Considering that future foundations load the bedrock in a similar direction as the axial loaded point load tests, then more emphasis is placed on these results.

Assuming a UCS/Is50 correlation factor of 15, the inferred UCS values for all the point load test results, when loaded axially, are estimated to be approximately 6.08 MPa to 20.0 MPa, with an average of 13.81 MPa.



6. Discussion

6.1 Geotechnical Issues

The presence of an uncontrolled waste fill layer is the primary geotechnical issue or constraint at the site. The was layer consists of municipal waste placed across most of site between the 1940s and 1980s. The former landfill was not properly closed or capped and does not include provisions for the management of leachate and gas (Edison, 2020). Rather than being formally capped, waste was covered with a layer of predominately sand soil with gravel and minor construction waste (i.e. brick and concrete) and finished off with a thin layer of topsoil and grass. The base of the landfill waste layer ranges from approximately 1 m around the perimeter of the landfilled area (Figure 2) and up to approximately 9 m. Undulations in the existing playing surfaces are a direct consequence of the differential settlement of uncontrolled waste fill material and the degradation of the municipal waste.

A secondary geotechnical issue is the inconsistency of the alluvium underlying the waste. Alluvium varies from very loose to loose to medium dense and dense and therefore minimises any confidence on this layer being a suitable bearing stratum for the major structures that are proposed on the site, namely the tiered seating area and amenities building).

6.2 Site Preparation

Prior to construction of the proposed new structures and the artificial grass fields, all topsoil with organic matter and any pavement materials, should be removed. Stripped topsoil should be stockpiled for re-use as landscape material or disposed off-site.

Material removed from site will need to be managed in accordance with the provisions of current legislation and may include segregation by material type classification in accordance with NSW EPA (2014) *Waste Classification Guidelines* and disposal at facilities appropriately licensed to receive the particular materials.

6.3 Pavement Subgrade Preparations and Design

The proposed development is expected to comprise a number of flexible pavements including the access roads, car parking areas and a network of pedestrian and bicycle pathways. Flexible pavements are also expected to be adopted beneath the artificial grass playing fields.

Pavement designs are based on the CBR and the modulus of the subgrade materials, encountered after any excavation or re-grading has taken place. The principal aim of the subgrade preparation for pavements is to provide a uniform foundation so that there will be little risk of settlement (particularly differential settlement) over the long term.

Assuming minimal earthworks are undertaken as specified above, the final pavement subgrade across the site will likely comprise the general fill layer (i.e. Unit 2) which predominately comprises a mixture of silty and, sand and gravelly sand with minor construction waste (e.g. concrete and brick). This layer is considered suitable as a subgrade and will offer a relatively high CBR as indicated with the limited testing completed herein (refer to Section5.3.3). However, regardless of the suitability of the existing subgrade and its high CBR properties, differential settlements are expected to continue across the site as the underlying landfilled waste layer (Unit 3) continues to degrade.

There are a number of ways to manage the ongoing differential settlements and the final choice will depend on the project budget, available timeframe and sensitivity/tolerance of the final product is to differential settlements.



A solution which can prevent ongoing differential settlement occurring but is at the high end of the cost spectrum, is a suspended slab supported by piles founded through the fill layer and into competent natural soil profile or the bedrock formation. This methodology has recently been used for an artificial multi-use field in Lane Cove (Blackman Park), however, Edison expects that this is excessive and most likely cost-prohibitive for this project, especially for the proposed roads, carparks and cycleways.

A more cost-effective solution for significantly minimising future differential settlement is the use polypropylene geogrids to reinforce the pavement subgrade. The use of a geogrids is well established for improving the bearing capacity of soft soils and minimising differential settlement and localised settlements due to abruptly settling or subsiding weak zones, such as within a landfilled area. Essentially the tensile strength of the geogrid is combined with a layer of aggregate (including recycled aggregate) which has a greater rigidity, which in turn creates a composite layer which has a greater rigidity and stability than the individual layers alone.

Of the pavements proposed for this project, the artificial grass playing fields will be the most sensitive to differential settlements and from past experience, at least two layers of geogrid should be allowed for in the final budget. Whether geogrids are used to reinforce the subgrades of the other pavements will ultimately depend on the remaining project budget and whether future undulations and repairs are desired.

6.4 Foundations

6.4.1 Tiered Seating Area and Amenities Building

Given the subsurface conditions and the scale of the proposed development, a shallow foundation system is not recommended for the proposed grandstand and amenities building. The upper portion of the natural, alluvial soil profile is inconsistent with variable density and therefore, Edison recommends that footings are advanced using piles into the underlying bedrock formation. The use of CFA piling equipment is preferred for the ground conditions encountered and to reduce the possibility of Acid Sulfate Soils (ASS) associated with natural alluvium being brought to the surface.

Based on the limited information available, the depth to bedrock in the vicinity of these structures varies between 16.2m and 20.8m bgs with the depth to bedrock increasing towards the north-east. The upper portion (Unit 3a) of the bedrock formation appears to have inconsistent strength, before becoming consistently medium to high strength and at least Class III Sandstone in accordance with Pells *et al*, 2019. Preliminary design parameters are provided in **Table 6** for both Units 6a and 6b, however, Edison recommends that additional investigations are completed to confirm this quality and strength of bedrock is consistent across the entire building footprints.

Table 6: Preliminary Foundation Design Parameters

Founding Stratum	Serviceability Bearing Pressure (MPa)	End	Ultimate compressive Side Shear (kPa)	Elastic (Young's) Modulus (MPa)	Design Poisson's Ratio (γ)
Unit 6a Bedrock	0.7		50	50	0.3
Unit 6 b Bedrock	3.5		800	350	0.25

For piles, the above design parameters assume that the piles are socketed at least 0.5 m into the rock class and the ultimate side shear values assumes a rough socket of category R2 or better is achieved.



Settlements for footings on rock are anticipated to be less than about 1% of the pile diameter.

Finally, footing systems should be designed by a suitably qualified and experienced structural engineer and as CFA piling is a 'blind' piling technique (and hence not suited to geotechnical inspections), CFA piles would need to be certified by the piling contractor, to confirm that the piles have reached a suitable depth and that the material encountered is consistent with the design assumptions.

6.4.2 Minor Structures

For the other minor structures proposed in the Masterplan that are less susceptible to differential settlements caused by the landfilled layer, a raft slab may be adopted. If adopted, raft slabs may be designed based on a relatively conservative bearing capacity of 75kPa.

6.4.3 Aggressivity / Exposure Potential

Based on the limited exposure classification test results (Section 5.3.2), and in accordance with AS 2159-2009, the subsurface concrete structures (*e.g.* footings) should be designed based on severely-aggressive soil conditions for concrete. According to Australian Standard AS 3600-2009, the equivalent exposure classification is 'B2' which takes into account the highly saline fill layer. Any un-protected steel placed in contact with the fill and natural soil profile should be designed based on severely corrosive conditions.

6.5 Earthquake Design

Structural design for earthquake loads should be carried out in accordance with the relevant provisions in AS1170.4–2007. At this preliminary stage and with reference to Table 4.1 of AS1170.4, the site sub-soil class is considered to be D_e . This classification is provided because there were occasional SPT results of less than 6 which infers very loose soils are present, albeit sporadically.

6.6 Salinity

Laboratory testing completed as part of this preliminary geotechnical investigation indicates that subsurface fill and natural soil profile is very saline. Considering there are no major earthworks proposed for the site, a site-specific salinity management plan is not warranted. However, the salinity levels should be considered when designing concrete elements in contact with the fill and natural soil profile.

6.7 Stormwater Infiltration

Based on the *in-situ* permeability testing conducted as part of this investigation and taking into account Rockdale Councils' 'Technical Specification: Stormwater Management', an absorption system to manage stormwater from future structures is unlikely to be feasible. Considering permeability test results and the requirement to mitigate potential landfill leachate and gas generation by minimising infiltration, an alternative system is recommended.



7. Conclusion and Recommendations

Sufficient information has been gained to be confident of the subsurface conditions across the site and to broadly identify geotechnical constraints to implementation of the Masterplan and to assist with the preliminary design.

Based on the results of the investigation, the proposed Masterplan development is considered feasible. However, further investigation is recommended to define the strength and quality of the bedrock formation more accurately beneath the proposed new grandstand and amenities building.



8. General Limitations

Soil and rock formations are variable. The logs or other information presented as part of this report indicate the approximate subsurface conditions only at the specific test locations. Boundaries between zones on the logs or stratigraphic sections are often not distinct, but rather are transitional and have been interpreted.

The precision with which subsurface conditions are indicated depends largely on the frequency and method of sampling, and on the uniformity of subsurface conditions. The spacing of test sites also usually reflects budget and schedule constraints. Groundwater conditions described in this report refer only to those observed at the place and under circumstances noted in the report. The conditions may vary seasonally or as a consequence of construction activities on the site or adjacent sites.

Where ground conditions encountered at the site differ significantly from those anticipated in the report, either due to natural variability of subsurface conditions or construction activities, it is a condition of this report that Edison be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of changed soil and rock conditions requires experience and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

The comments given in this report are intended only for the guidance of the design engineer, or for other purposes specifically noted in the report. The number of boreholes or test excavations necessary to determine all relevant underground conditions which may affect construction costs, techniques and equipment choice, scheduling, and sequence of operations would normally be greater than has been carried out for design purposes. Contractors should therefore rely on their own additional investigations, as well as their own interpretations of the borehole/test pit data in this report, as to how subsurface conditions may affect their work.



9. References

Australian Standards, 2004. AS1289.6.3.1 Methods of testing soils for engineering purposes - Soil strength and consolidation tests - Determination of the penetration resistance of a soil - Standard Penetration Test.

Australian Standard (AS) 2159 -2009: Piling Design and Installation.

Australian Standard (AS) 3600 –2009: Concrete Structures.

Australian Standard (AS) 1170.4-2007. Structural design actions Part 4: Earthquake actions in Australia.

Consulting Earth Scientists, 2001a: Phase I Environmental Site Assessment: Cooks Cove Development Site. Prepared for Trafalgar Properties Pty Ltd and Page Kirkland Management Pty Ltd. Report ID: CES010403-TRF-01-D1. 2 August 2001.

Consulting Earth Scientists, 2008a: Report on Additional Soil, Groundwater and Landfill Gas Assessment. Report ID: CES050706-BCC-16-F - Area C. 4 August 2008.

Consulting Earth Scientists, 2008b: *Report on Additional Soil, Groundwater and Landfill Gas Assessment. Report ID: CES050706-BCC-19-F - Area D.* 5 August 2008.

Consulting Earth Scientists, 2016a: *Area D1 Preliminary Stage 2 Environmental Site Assessment and Area C Groundwater Monitoring Event Report, Cooks Cove, Bestic Street, Banksia, NSW.* Report ID: CES130608-BP-AJ. 12 February 2016.

Consulting Earth Scientists, 2017b: *Draft Detailed Design Remediation Action Plan, Cook Cove Southern Precinct, Arncliffe & Banksia, NSW.* Report ID: CES130608-BP-BC. 11 July 2017.

Department of Mineral Resources, 1983: Sydney 1:100,000 Geological Series Map Sheet 9130 (Edition 1).

Department of Environment, Climate Change and Water, 2009: Sydney 1:100 000 Soil Landscape Series Sheet 9130 (fourth edition).

Department of Land and Water Conservation NSW, 2002: Site investigations for urban salinity.

Edison Environmental & Engineering Pty Ltd, 2020: *Report on Site Suitability for Recreational/Open Space, Barton Park, New South Wales*. Report E17011-CU-05-R Rev 2 8 January 2020. Prepared for Bayside Council.

Hvorslev, M. J., 1949: *Time lag in the observation of ground-water levels and pressures*. US Army Waterways Experiment Station, Vicksburg Miss.

Lambe and Whitman, 1969: Soil Mechanics. John Wiley & Sons.


Maunsell McIntyre, 2001: Cooks Cove Master Plan, Site History Geotechnical and Contamination Issues – Desk Top Study. Report ID: 20091000.12. 6 March 2001.

New South Wales Environment Protection Authority (NSW EPA), 2014: Waste Classification Guidelines – Part 1 Classifying Waste. November 2014.



Pells, P. J. N., Mostyn, G., Bertuzzi, R., and Wong, P.K., 2019: *Classification of Sandstones and Shales in the Sydney Region: A Forty Year Review.* Australian Geomechanics Society, Volume 54 No. 2 June 2019.

Rockdale City Council, 2011 (RCC, 2011): *Rockdale Technical Specification Stormwater Management*. Adopted 4 May 2011 effective 5 December 2011.



ENVIRONMENTAL + ENGINEERING



EDISON

SITE PLAN
Barton Park, Bestic Street, Rockdale NSW

 SCALE:
 N.T.S
 DATE:
 20 Aug 2020
 FIGURE No.
 2

 DRAWN:
 S. McC
 JOB No.:
 E17011-CU
 REVISION:
 A




EDISON ENVIRONMENTAL + ENGINEEDING

BOREHOLE LOCATIONS (Aerial)
Barton Park, Bestic Street, Rockdale NSW

 SCALE:
 N.T.S
 DATE:
 20 Aug 2020
 FIGURE No.
 3

 DRAWN:
 S. McC
 JOB No.:
 E17011-CU
 REVISION:
 A




BOREHOLE LOCATIONS (Masterplan) DRAWN: JOB No.: REVISION: Barton Park, Bestic Street, Rockdale NSW S. McC E17011-CU Α



FIGURES



ANNEXURE 1: Survey and Masterplan of the Proposed Development

































ANNEXURE 2: Previous Borehole Logs and Site Plan





Cooks Cove

Easting: 329290.10

Elevation: 1.98

Client: **Boyd Cook Cove**

Project:

Northing: 6242415.23



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH801

	DRILLING INFO.			LITHOLOGY	SAMPLING INFORMATION							
pth	Method	Water	Symbol	Description	Sample ID	Туре	0	F ID/	PID		m)	WELL DETAIL
								5),	5	2	
-	\uparrow			FILL: Grass/topsoil, silty sand, brown, dry. loose, fine grained, minor gravel up to 5mm diameter								
- - - -				FILL: Silty sand, brown, dry, loose, fine grained, sandstone up to 25mm in diameter, minor paint flecks/pieces (blue) up to 10mm in diameter								
-				FILL: Crushed sandstone, weathered, white/orange, dry								
-	—— Direct Push			FILL: Sandy clay, brown/orange, moist, soft, fine grained, minor sandstone up to 10mm in diameter, minor gravel up to 15mm diameter								
-			- :-/- - :-/-	SILTY CLAY: Dark grey to black, moist, soft, organic matter								
- - -				SILTY SAND: Grey/brown, wet, loose, fine grained, organic matter								
- - - - -				End of borehole.								

Macquarie Drilling **Drill Company:**

Drill Model: Geoprobe 7720DT

Hole Diameter (mm): 83

13/05/2008 **Date Commenced:**

Date Completed: 13/05/2008

Logged/checked by: Philip Norris

Easting: 329402.18

Cooks Cove

Northing: 6242389.69

Elevation: 1.43

Client: **Boyd Cook Cove**



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Project:

Environmental Log: DBH802

DF	RILLING	INFO.		LITHOLOGY	SAMF	LING INF	FORMATION	
Depth	Method	Water	Symbol	Description	Sample ID	Туре	0 500 500 500 500	WELL DETAIL
0	,			J		_		
-	\uparrow			FILL: Roadbase				
-	ysr			FILL: Silty sand, dark grey, dry, loose, fine grained, gravel up to 10mm in diameter				
	Direct Push			FILL: Sandy clay, brown/orange, moist, soft, fine grained, minor sandstone up to 5mm in diameter, minor organic matter				
1-				SANDY CLAY: Dark grey/black, moist, soft, fine grained, organic matter				
-				End of borehole.				
2								
_								
- - - - -								
3								***
- - - -								
4-								
5								

Macquarie Drilling **Drill Company:**

Drill Model: Geoprobe 7720DT

Hole Diameter (mm): 83

13/05/2008 **Date Commenced:**

Date Completed: 13/05/2008

Logged/checked by: Philip Norris

Cooks Cove

Boyd Cook Cove

Easting: 329281.57

Project:

Client:

Northing: 6242316.46

Elevation: 1.31



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove **Environmental Log: DBH803**

DR	ILLING	INFO.		LITHOLOGY	SAMP	LING IN	IFORMATION	
Depth	Method	Water	Symbol	Description	Sample ID	Туре	FID/PID (ppm) 0 2200 292	WELL DETAIL
0			JI				(4 4) 14	_
	Hand Au			FILL: Silty sand, brown, dry, loose, fine grained, brick up to 10mm diameter, slag/ash material up to 10mm diameter, basalt up to 20mm diameter, minor sandstone (crushed)				
-				minor sandstone (crushed)				
]				FILL: Refusal				
1-				End of borehole.				
1								
-								
1								
2								
-								
1								
3								
-								
1								
-								
4								
\parallel								
1								
1								
\parallel								
5				L	1	'		

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 75

15/05/2008 **Date Commenced:**

Date Completed: 15/05/2008

Logged/checked by: Philip Norris

Easting: 329449.64

Project: Cooks Cove

Northing: 6242314.30

o **=**

CONSULTING EARTH SCIENTISTS

Client: Boyd Cook Cove

Elevation: 1.05

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH804

DF	RILLING	INFO.		LITHOLOGY	SAMP	LING IN	FORMATION	
Depth	Method	Water	Symbol	Description	Sample ID	Туре	FID/PID (ppm) 0 250 092 2	WELL DETAIL
0			JI				(\ u) \	
-	h —			FILL: Grass/topsoil, silty sand, brown, moist, loose, fine grained, gravel up to 10mm diameter, sandstone up to 20mm diameter				
-	Direct Push			FILL: Extremely weathered shale, silt, light grey, dry to moist, minor organic matter				
1-				FILL: Silty sand, dark grey/black, moist to wet, loose, medium grained, gravel up to 10mm diameter, slag/ash material up to 20mm diameter, plastic, timber fragments, slight landfill odour				
-								
- - - -				End of borehole.				
2-								
- - - - -								
3-								
- - - -								
- - - -								
4-								
5								

Drill Company: Macquarie Drilling

Drill Model: Geoprobe 7720DT

Hole Diameter (mm): 83

Date Commenced: 13/05/2008

Date Completed: 13/05/2008

Logged/checked by: Philip Norris

Easting: 329586.28

Project: Cooks Cove

Northing: 6242322.97

Client: Boyd Cook Cove

Elevation: 5.89



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH805

DF	RILLING	INFO.		LITHOLOGY	SAMP	LING IN	FORMATIO		MEI
Depth	Method	Water	Symbol	Description	Sample ID	Туре	0 FID/PID 0 520		WELL DETAIL
0						_			
-	\uparrow			FILL: Grass / topsoil (silty sand)					
- - - -	Auger Solid Flight –			FILL: Silty sand, brown, dry, loose , medium grained, minor clay, sandstone up to 10mm in diameter, ironstone up to 10mm in diameter					
	er So			FILL: Brick/tile rubble					
1-	— Auge			FILL: Silty sand, brown, dry, loose, fine - medium grained, minor gravel, sandstone up to 10mm in diameter					
	V			FILL: Silty sand, dark grey, dry, loose, medium - coarse grained, minor gravel, minor slag/ash material, waste material - plastic, glass, timber. No ACH observed in fill material					
2				End of borehole.					
-									
3-									
-									
4-									
5][]			I		40/04/6	

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 10/04/2008

Date Completed: 10/04/2008

Logged/checked by: Philip Norris

Easting: 329720.33

Project: Cooks Cove

Northing: 6242291.53

Client: Boyd Cook Cove

101 tilling. 02 12201.

Elevation: 6.30



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH806

DR	ILLING	INFO.		LITHOLOGY	SAMP	LING INF	FORMATION	
Depth	Method	Water	Symbol	Description	Sample ID	Туре	0 750 (ppm) 0 250	WELL DETAIL
0	,			,				
-	Auger Solid Flight ———			FILL: Grass / topsoil (silty sand) FILL: Silty sand, brown, dry, loose, fine grained, brick up to 40mm diameter, concrete up to 25mm in diameter				
1-	— Auger 8			FILL: Silty sand, brown, dry, loose, fine grained, brick up to 40mm diameter, concrete up to 25mm in diameter				
				FILL: Silty sand, brown, dry, loose, medium grained, minor clay, gravel up 10mm diameter, sandstone up to				
2				10mm diameter, sandstone up to 20mm diameter, fibrous material present - pieces up to 10mm in diameter (possible ACH) End of borehole.				

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 04/04/2008

Date Completed: 04/04/2008

Logged/checked by: Philip Norris

. . .

Easting: 329514.62

Cooks Cove

Boyd Cook Cove

Northing: 6242273.96

Elevation: 6.62



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Project:

Client:

Environmental Log: DBH807

אט	ILLING	INFO.		LITHOLOGY	SAMI	PLING IN				
epth	Method	Water	Symbol	Description	Sample ID	Туре	1 D/PI	D (p	pm) 220	WELL DETAIL
			11				.,	υ,		
-	\uparrow			FILL: Grass / topsoil (silty sand)						
- - - - -	Auger Solid Flight ———			FILL: Silty sand, light brown, dry, loose, medium grained, minor ironstone up to 10mm diameter, minor gravel, sandstone up to 15mm diameter, minor glass pieces up to 5mm diameter						
	—— Auger Sc			FILL: Sandy clay, dark brown to black, moist, stiff, fine - medium grained, brick up to 20mm diameter, sandstone up to 10mm diameter, minor gravel, minor glass pieces up to 5mm in diameter						-
1	\downarrow			FILL: As above. Slight landfill odour, waste material present - plastic, metal,						
-				ceramic, timber. Note - No asbestos material observed						
-				End of borehole.						
- - - - - - -										

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 04/04/2008

Date Completed: 04/04/2008

Logged/checked by: Philip Norris

Cooks Cove


Easting: 329584.09

Northing: 6242278.55

Client: Boyd Cook Cove

Project:

Elevation: 6.16



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH808

Depth Method Water Symbol Description Sample ID Type So	VELL DETAIL
FILL: Grass / topsoil (silty sand) FILL: Silty sand, brown to dark brown, dry, loose, medium grained, minor concrete, slag - ash material, glass pieces (up to 10mm diameter), brick, minor fibrous material present (up to 10mm diameter), crushed sandstone FILL: As above, slight landfill odour, timber, plastic, metal present End of borehole.	
End of borehole.	
End of borehole.	
End of borehole.	

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 04/04/2008

Date Completed: 04/04/2008

Logged/checked by: Philip Norris

Boyd Cook Cove

Easting: 329633.92

Project: Cooks Cove **Northing:** 6242251.35

Elevation: 5.77

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

10/04/2008

10/04/2008

Philip Norris

Sheet: 1 of 1

Date Commenced:

Logged/checked by:

Date Completed:

CONSULTING

SCIENTISTS

Client: Location:

Cooks Cove

Environmental Log: DBH809

DR	ILLING	INFO.		LITHOLOGY	SAMI	PLING INF	FORMATION	
epth	Method	Water	Symbol	Description	Sample ID	Туре	FID/PID (ppm) 0 250 250 250	WELL DETA
0								
,	\uparrow			FILL: Grass / topsoil (silty sand)	λ			
1	ļ			FILL: Silty sand, brown, grey, dry,				
7	-ligh			loose				
1	Auger Solid Flight			FILL: Sandstone rubble	-			
1	er S			FILL: Silty sand, grey - dark brown,				
1	Aug			drv. loose, medium grained, minor				
1				gravel, sandstone up to 20mm diameter, brick up to 30mm in diameter, minor concrete, slag/ash				
+	\downarrow			diameter, minor concrete, slag/ash material, minor glass/ceramic.		-		
1								
7				End of borehole.				
1								
+								
1								
1								
7								
1								
+								
1								
1								
\parallel								
1								
$\frac{1}{2}$								
1								
1								
-								
1								
1								
$\frac{1}{2}$								
1								
4								

Macquarie Drilling

Geoprobe 6620DT

Drill Company:

Hole Diameter (mm): 125

Drill Model:

Project:

Location:

Cooks Cove

Cooks Cove

Easting: 329273.90

Northing: 6242228.60

, 📑


CONSULTING

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Client: Boyd Cook Cove

Elevation: 0.86

Environmental Log: DBH810



Drill Company: Macquarie Drilling

Drill Model: Geoprobe 7720DT

Hole Diameter (mm): 83

Date Commenced: 13/05/2008

Date Completed: 13/05/2008

Logged/checked by: Philip Norris

Lastii

Easting: 329377.51

Elevation: 5.44

CONSULTING EARTH SCIENTISTS

Project: Cooks Cove

Boyd Cook Cove

Northing: 6242226.88

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Client:

Environmental Log: DBH811

DR	ILLING	INFO.		LITHOLOGY	SAME	PLING IN	FOR	MA	LION	l	
anth	Mathad	Water	Cumb al	Deceription	Samula ID	Time	F	FID/F	PID (opm)	WELL DETAIL
eptn	Method	water	Symbol	Description	Sample ID	Туре	0	250	200	750	
) 	\uparrow			FILL: Grass / topsoil (silty sand)							
	ght —			FILL: Silty sand, dry, loose, grey, fine grained, gravel up to 20mm diameter							
	Auger Solid Flight			FILL: Silty sand, dark grey, dry, loose, medium grained, minor brick up to 5mm diameter. minor concrete up to							
	Auger			5mm in diameter FILL: Silty sand, dark grey, dry, loose.							
	\downarrow			fine grained, brick up to 10mm diameter, minor gravel, slight landfill odour, waste material present - timber,							
1				glass, metal, ceramic							
+											
1											
4				End of borehole.							
+											
1											
4											
+											
1											
4											
+											
1											
1											
\dashv											
1											
1											
4											
+											
1											
]											
-											
ı-							ļļ				
1											
\parallel											
+											
]											
\parallel											
- II			11			- 1					

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 04/04/2008

Date Completed: 04/04/2008

Logged/checked by: Philip Norris

Cooks Cove

Easting: 329371.11

Northing: 6242149.85

Client: Boyd Cook Cove

Project:

Elevation: 4.97

EARTH SCIENTISTS

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH812

DK	ILLING	INFO.		LITHOLOGY	SAME	PLING IN				
pth	Method	Water	Symbol	Description	Sample ID	Туре	D/PII	O (p)	9m)	WELL DETAI
							<u> </u>	2		<u> </u>
) 	\uparrow			FILL: Grass / topsoil (silty sand)						
- - -	— Auger Solid Flight			FILL: Silty clay, dark brown/black, moist, soft, fine grained, brick up to 20mm diameter, minor gravel, sandstone up to 20mm diameter						
	← Auger			FILL: Dark brown - black, moist, soft, coarse grained sand, brick up to 20mm diameter, minor gravel, sandstone up to 20mm diameter, landfill odour, waste material - metal,						
				glass, plastic, timber. No asbestos material observed						
- - -				End of borehole.						
-										
-										
- - - -										

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 04/04/2008

Date Completed: 04/04/2008

Logged/checked by: Philip Norris

Easting: 329316.28

Cooks Cove

Northing: 6242132.16

Boyd Cook Cove Client:

Project:

Elevation: 5.31



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove **Environmental Log: DBH813**

DR	ILLING	INFO.		LITHOLOGY	SAMI	PLING IN	FORI	MAT	ION	I		
pth	Method	Water	Symbol	Description	Sample ID	Туре	• F	FID/P 520	1 D (p		n)	WELL DETAIL
]					7	ũ			
7	\uparrow			FILL: Grass / topsoil								
1	light -			FILL: Silty sand, brown, dry, loose, fine grained, gravel up to 15mm diameter								
	Auger Solid Flight			FILL: Clayey sand, moist, soft, fine to medium grained, brown, sandstone (red/orange) up to 20mm diameter,								
	– Augei			gravel, potential asbestos material (white / fibrous), ironstone up to 10mm diameter								
1	\downarrow			FILL: Silty sand, dark grey, moist,								
				loose, medium to coarse grained, landfill odour, sandstone up to 20mm diameter, ironstone up to 10mm diameter, concrete, gravel up to 5mm diameter								
4				End of borehole.								
1				2.10 0. 50.010.01								
+												
1												
1												
1												
7												
1												
4												
1												
4												
1												
$\frac{1}{2}$												
1												
+												
1												
+												
]												
1												
1												
JL						I						

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

01/04/2008 **Date Commenced:**

Date Completed: 01/04/2008

Logged/checked by: Philip Norris

Cooks Cove

Easting: 329302.17

Northing: 6242073.62

62

CONSULTING EARTH SCIENTISTS

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Client:

Project:

Boyd Cook Cove

Elevation: 5.01

Location: Cooks Cove Environmental Log: DBH814

DRILLING INFO.			LITHOLOGY	SAME	LING IN	FORI	MAT	ION	WELL DETAIL			
epth	Method	Water	Symbol Description		Sample ID	Туре	FID/PID (ppm) ype 0 02 09 092			WELL DETAIL		
0												
	\uparrow			FILL: Grass / topsoil								
	Auger Solid Flight →			FILL: Silty sand, brown, moist, loose, medium grained, slag/ash material up to 20mm diameter, minor clay, plastic, ceramic up to 10mm diameter, minor gravel								
-	← Auger			FILL: Silty sand, dark grey - black, medium - coarse grained, moist, loose, 20mm diameter, minor gravel, landfill odour, waste material - metal, glass,								
-				ceramic, plastic. Note - No asbestos material observed								
				End of borehole.								
.												
- - - - -												
-												
-												
, — - - - - - - -												

Drill Company: Macquarie Drilling

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 01/04/2008

Date Completed: 01/04/2008

Logged/checked by: Philip Norris

Boyd Cook Cove

Easting: 329269.68

Elevation: 5.10

Project: Cooks Cove

Client:

Northing: 6242031.29

SCIENTISTS Jones Bay Wharf 19-21, Lower Level Suite 121

26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

CONSULTING

Location: Cooks Cove

Environmental Log: DBH815

DRILLING INFO.				LITHOLOGY	SAMPLING INFORMATION FID/PID (ppm)						J
pth	Method	Water	Symbol	Description	Sample ID	Туре			D (p) 200	9m)	WELL DETAII
1			JL	JL.					4,	14	
7	\uparrow			FILL: Grass / topsoil							
-	Auger Solid Flight ——			FILL: Silty sand, brown, dry loose, fine grained, minor sandstone up to 10mm diameter, minor clay, minor slag/ash material up to 10mm diameter, minor charcoal material (fragments up to 5mm diameter)							
- - -	- Auger S			FILL: Same description as above. Slight landfill odour, brick up to 20mm diameter, plastic, metal, tile (waste material)							
-	\downarrow			FILL: Silty clay, dark grey, moist, soft, fine grained, minor shell fragments. Note - No asbestos material observed							
_ _ _ _				End of borehole.							
-											
- - - - -											

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

01/04/2008 **Date Commenced:**

Date Completed: 01/04/2008

Logged/checked by: Philip Norris

Cooks Cove

Easting: 329345.55

Elevation: 4.17

Northing: 6242010.72

Client: **Boyd Cook Cove**



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Project:

Environmental Log: DBH816

DRILLING INFO.				LITHOLOGY	SAMF			
Depth	Method	Water	Symbol	Description	Sample ID	Туре	FID/PID (ppm) 0 250 250 250	WELL DETAIL
0	,			J.		_		
- - - -				FILL: Silty sand, brown to dark, dry, loose, fine grained, brick fragments, sandstone up to 10mm diameter				
- - - -	Flight —			FILL: Silty sand, brown to dark, dry, loose, fine grained, brick fragments, sandstone up to 10mm diameter				
1-	Auger Solid Flight			FILL: Silty sand, brown to dark, dry, loose, fine grained, brick fragments, sandstone up to 10mm diameter				
				FILL: Silty sand, dark grey, moist, loose, fine grained				
2	\			FILL: Silty sand, dark grey to black, moist, loose, fine grained, landfill odour, waste material - glass, ceramic, metal. Note - No asbestos material observed				
-				End of borehole.				
3-								
-								

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

01/04/2008 **Date Commenced:**

Date Completed: 01/04/2008

Logged/checked by: Philip Norris

Boyd Cook Cove

Easting: 329205.83

Cooks Cove

Northing: 6241996.58

Elevation: 1.27



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Project:

Client:

Environmental Log: DBH817

WELL DETAIL
17

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

07/04/2008 **Date Commenced:**

Date Completed: 07/04/2008

Logged/checked by: Philip Norris

Easting: 329264.22

Cooks Cove

Northing: 6241986.87

Boyd Cook Cove Client: Elevation: 4.87 SCIENTISTS

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

CONSULTING

Location: Cooks Cove

Project:

Environmental Log: DBH818

DRILLING INFO.				LITHOLOGY	SAMF	LING IN	FORM	AT	ION		WELL DETAIL		
nth	Mothod	Water	Symbol	Description	Sample ID	Timo			D (p		WELL DETAIL		
	Method	vvater	Symbol	Description	Sample ID	Туре	0	250	200	750			
7	\uparrow			FILL: Grass / topsoil (silty sand)									
1	Flight			FILL: Brown, dry, loose, fine grained, gravel, sandstone up to 20mm									
1	Solid			diameter FILL: Dark grey - black, loose, dry,									
	← Auger Solid Flight →			coarse grained, basalt up to 45mm diameter, slag/ash material, sandstone up to 20mm diameter, minor gravel, slight landfill odour, waste material -									
T				timber, glass, metal. Note - No asbestos material observed									
				End of borehole.									
1													
1													

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

04/04/2008 **Date Commenced:**

Date Completed: 04/04/2008

Logged/checked by: Philip Norris

Cooks Cove

Easting: 329276.15

Elevation: 4.64

Northing: 6241919.63

Client: Boyd Cook Cove

umg. 02+1010.0



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Project:

Environmental Log: DBH819

DRILLING INFO.				LITHOLOGY	SAMPLING INFORMATION FID/PID (ppm)					MELL DETAIL		
pth	Method	Water	Symbol	Description	Sample ID	Туре	0	FID 027		20 20 20	pm 220	WELL DETAIL
								N		LΩ		
7	\uparrow			TOPSOIL: Grass								
-				FILL: Silty sand, brown, dry, loose, fine grained, minor gravel								
	Auger Solid Flight			FILL: Clayey sand, grey/brown, dry, loose, fine grained, minor gravel, minor sandstone (crushed)								
-	Auger So			FILL: As above, waste material - metal, plastic, timber, glass, slight landfill odour								
-				FILL: As above								
- -	<u> </u>		XXXX									
1				End of borehole.								
_												
1												
-												
1												
1												

Drill Company: Macquarie Drilling

Hydrapower Scout V

Hole Diameter (mm): 125

Drill Model:

Date Commenced: 07/04/2008

Date Completed: 07/04/2008

Logged/checked by: Philip Norris

Project:

Location:

Easting: 329192.66

Cooks Cove

Cooks Cove

Northing: 6241904.46

Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

07/04/2008

07/04/2008

Philip Norris

Sheet: 1 of 1

Date Commenced:

Logged/checked by:

Date Completed:

CONSULTING

SCIENTISTS

Boyd Cook Cove Client:

Elevation: 1.34

Environmental Log: DBH820

DRILLING INFO.				LITHOLOGY	SAMPLING INFORMATION FID/PID (ppm)								ve
Depth	Method	Water	Symbol	Description	Sample ID	Туре	0	FID/ 520	PID	(p	0m)	\ \ \	VELL DETAIL
0						_							
-	\uparrow			TOPSOIL: Grass									
- - -	light ——			FILL: Silty sand, brown, dry to moist, loose, medium grained, minor gravel, sandstone up to 10mm diameter, slag/ash material									
	Auger Solid Flight			SANDY CLAY: Brown/orange, moist, soft, fine grained, ironstone up to 5mm diameter, organic matter									
1-	— Auge			SAND: Light grey, wet, loose, fine to medium grained									
-	\downarrow			CLAYEY SAND: Grey, wet, loose, fine grained									
2				End of borehole.									
-													
3-													
-													
4 -													

Macquarie Drilling

Hydrapower Scout V

Drill Company:

Hole Diameter (mm): 125

Drill Model:

Easting: 329269.14

Project: Cooks Cove **Northing:** 6241861.07

Boyd Cook Cove Client:

Elevation: 4.19



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Environmental Log: DBH821

DRILLING INFO.				LITHOLOGY	SAMP						
Depth	Method	Water	Symbol	Description	Sample ID	Туре	FI o	D/PI	D (pp	m)	WELL DETAIL
0			JL	· · ·					4,		
-	\uparrow			TOPSOIL: Grass							
- - - -	light ——			FILL: Silty sand, brown, dry, loose, medium grained, minor gravel, sandstone up to 20mm diameter, brick up to 10mm diameter							
1	Auger Solid Flight			FILL: Silty sand, dark brown, dry to moist, loose, fine to medium grained, basalt up to 40mm diameter, minor sandstone, minor gravel							
' - - -	At At			FILL: Silty sand, dark grey/black, moist, loose, fine grained, gravel, minor sandstone (crushed)							
	\downarrow			FILL: As above, waste material - plastic, metal, glass, timber, slight							
2				End of borehole.							
-											
3											
4											

Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

07/04/2008 **Date Commenced:**

Date Completed: 07/04/2008

Logged/checked by: Philip Norris

Project ID: CES050706-BCC

Boyd Cook Cove

Easting: 329719.72

Elevation: 1.50

Project: Cooks Cove **Northing:** 6242245.15



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399

Location: Cooks Cove

Client:

Environmental Log: DMW803A

DR	ILLING	INFO.		LITHOLOGY	SAME	FORMATION			WELL BETAIL		
pth	Method	Water	Symbol	Description	Sample ID	Туре	0	FID/ 520	P ID ()	220 pm)	WELL DETAI
				-1		_				•	
+	\uparrow			TOPSOIL: Grass							
				FILL: Concrete/sandstone rubble, minor roadbase							
				FILL: Silty sand, brown, dry, loose, fine grained, sandstone (crushed)							
- - -				FILL: Silty sand, dark brown, moist, loose, fine grained, minor bitumen/concrete, waste material - timber, glass, plastic							
	Direct Push —————			SILTY SAND: Dark brown to dark grey, wet, loose, minor organic matter, slight organic odour							
-											
1											
	\downarrow			SAND: Light grey, fine to medium grained, wet, loose							
-				End of borehole.							
1											

Macquarie Drilling **Drill Company:**

Drill Model: Geoprobe 6620DT

Hole Diameter (mm): 83

10/04/2008 **Date Commenced:**

Date Completed: 10/04/2008

Logged/checked by: Philip Norris

Project ID: Easting: 329455.13

Project: Cooks Cove Northing: 6242031.24



Suite 3, Level 1

Client: **Boyd Cook Cove** Elevation: 2.05

55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove **Environmental Log: DMW805**

DRILLING INFO.	LITHOLOGY	SAMPLING INFORMATION	WELL DETAIL
Depth Method Water	Symbol Description	Sample ID Type O SO OS SO S	WELL DETAIL
1 1 2 3 3 7 4 4 7 4 7 4 7 4 7 7 7 7 7 7 7 7 7	FILL: Grass and topsoil FILL: Silty sand, brown, dry, loose, fine grained, sandstone up to 15mm diameter, glass up to 15mm diameter FILL: Clayey sand, dark grey to black, moist, soft, fine grained, waste material present - timber, paint chips, glass, hydrocarbon odour FILL: Silty sand, moist, loose, fine grained, grey. Groundwater intersected @ 1.8m FILL: Clayey sand, dark brown, wet, soft, fine grained, minor organic matter (roots) FILL: Silty sand, grey, wet, loose, fine grained. Note - No asbestos material observed FILL: Silty sand, grey, wet, loose, fine grained. Note - Borehole over drilled 4.0 - 5.0m to compensate for collapse	22	
5	FILL: Silty sand, grey, wet, loose, fine grained End of borehole.		

Drill Company: Macquarie Drilling

Hydrapower Scout V **Drill Model:**

Hole Diameter (mm): 125

Date Commenced: 01/04/2008

Date Completed: 01/04/2008

Logged/checked by: Philip Norris

Project ID: CES050706-BCC

Easting:

Project: Cooks Cove



Jones Bay Wharf 19-21, Lower Level Suite 121 26-32 Pirrama Road Pyrmont 2009 PH: (02) 8569 2200 FAX: (02) 9552 4399


Client:

Boyd Cook Cove

Elevation:

Northing:

Cooks Cove Environmental Log: DMW806A



Macquarie Drilling **Drill Company:**

Drill Model: Hydrapower Scout V

Hole Diameter (mm): 125

Date Commenced: 07/04/2008

Date Completed: 07/04/2008

Logged/checked by: Philip Norris

Project: Environmental Site Assessment

Northing:

CONSULTING EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

111. (02) 0303 2200 1 AX. (0

Location: Bestic St, Banksia - Cook Cove Dev. Environmental Log: D1MW1

DRILLING INF	о.		LITHOLOGY	SAMF						
Depth Method W	ator Sv	mbol	Description	Sample ID	Type	PID (ppm)			Well Construction	
Depth Method W	ster Sy		Topsoil: Brown, sandy soil, organic matter FILL: Clayey SAND: dark brown, fine - medium grain, medium- high plasticity, dry-moist, wood, rock and brick fragments, pieces of plastic and glass, hydrocarbon odour low -medium plasticity from 1.8 metres moist at 1.8 metres wet at 2.2 metres	D1MW1-1 QA/QC101 QA/QC102 D1MW1-2	Type	0 027		750		
3- Vander 1 1 1 1 1 1 1 1 1			CLAY: Clayey SAND: grey/brown, fine grained, low plasticity, wet, sulphuric odour Possibly natural (PASS)	D1MW1-4						
6										

Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 19 October 2015

Date Completed: 19 October 2015

Logged/checked by: WS

Project: Environmental Site Assessment

Northing:


CONSULTING EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Bestic St, Banksia - Cook Cove Dev. Environmental Log: D1MW2



Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 20 October 2015

Date Completed: 20 October 2015

Logged/checked by: WS

Project: Environmental Site Assessment

Northing:

EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Bestic St, Banksia - Cook Cove Dev. Environmental Log: D1MW3

DRILLING INFO. **LITHOLOGY SAMPLING INFORMATION** Well Construction PID (ppm) Depth Method Water Symbol Description Sample ID Type Topsoil: Brown FILL: Clayey SAND: brown, finemedium grain, high plasticity, dry-D1MW3-1 moist, rock fragments QA/QC103 FILL: Clayey SAND: dark brown, fine grained, medium-high plasticity, drymoist, rock and glass fragments, wood material. hydrocarbon odours D1MW3-2 Abundant amounts of wood materials from approximately 2.0 metres Wet at approximately 4.2 metres Oil sheen from 4.0 metres D1MW3-3 Auger D1MW3-4 5 CLAY: Clayey SAND: Dark grey/brown, fine grained, low plasticity, wet, very slight sulphuric odour, peaty 6 8.□

Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 19 October 2015

Date Completed: 19 October 2015

Logged/checked by: WS

Bestic St, Banksia - Cook Cove Dev.

Project: Environmental Site Assessment

Northing:

EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Location:

Elevation:

Environmental Log: D1MW4

Location. Desi		IKSIA - COOK COVE DEV. LIN			D I IVIVV4		
DRILLING INFO.		LITHOLOGY	SAMF	LING INF	FORMATION		
Depth Method Water	Symbol	Description	Sample ID	Туре	PID (ppm)	Well Construction	
<u> </u>				- 71	0 250 500 750		
	\(\frac{1}{2}\)	Topsoil: Grey/brown, sandy, medium grain, organic material					
		FILL: Clayey SAND: grey/brown, fine-medium grain, medium-high plasticity,	D1MW4-1				
		dry, rock fragments, sub-angular shale, sandy in parts, hydrocarbon					
1 1		odour	D1MW4-2				
		FILL: Clayey SAND: dark brown/black, fine-medium grained, medium plasticity, moist, hydrocarbon odours, large amounts of wood materials, rock					
		fragments, cement fragments, pieces of wire and plastic, slight sheen	D1MW4-3				
		Water at 3.5 metres					
_ _ _ _			D1MW4-4				
3- Name 3- 1- 1- 1- 1- 1- 1- 1-				1			
4-]			D1MW4-5				
5-			D1MW4-6				
6							
7							

Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 19 October 2015

Date Completed: 19 October 2015

Logged/checked by: WS

Project: CES130806-BP

Location:

Northing:

CONSULTING EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Cooks Cove

Elevation:

Environmental Log: D1MW5

Depth Method Water Symbol Description Sample ID Type PID (ppm) Well Construct FILL: Gravelly SAND: brown, fine, dry, with angular gravel Presence of bricks around 1.5 metres Becoming dark brown FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay D1MW5_1.0-2.0 FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay D1MW5_3.0-4.0 D1MW5_4.0-5.0 D1MW5_5.0-6.0 This is a second of the sec	DRILLING INFO.		LITHOLOGY	SAMPL					
FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay D1MW5_3.0-4.0 D1MW5_4.0-5.0 D1MW5_5.0-6.0 D1MW5_5.0-6.0 D1MW5_6.0-7.0 D1MW5_6.0-7.0 D1MW5_6.0-7.0	Denth Method Water	Symbol	Description	Sample ID	Type				Well Construction
FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay, with waste Water at 5.8 metres Wire/cables at 7.0 metres Refusal terminated on account of steel cable/wire D1MW5_6.0-7.0 D1MW5_6.0-7.0	Depth Method Water	Syllibol	Description	Sample ID	туре	0	500	750	
FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay D1MW5_3.0-4.0 D1MW5_4.0-5.0 FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay, with waste Water at 5.8 metres Wire/cables at 7.0 metres Refusal terminated on account of steel D1MW5_6.0-7.0 D1MW5_7.0-7.2			with angular gravel Presence of bricks around 1.5 metres	D1MW5_0.0-1.0		•			
dry, with high plasticity clay D1MW5_2.0-3.0 D1MW5_3.0-4.0 D1MW5_4.0-5.0 D1MW5_5.0-6.0 dry, with high plasticity clay, with waste Water at 5.8 metres Wire/cables at 7.0 metres Refusal terminated on account of steel cable/wire D1MW5_6.0-7.0 D1MW5_6.0-7.0 D1MW5_7.0-7.2	1-			D1MW5_1.0-2.0		•	•		
FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay, with waste Water at 5.8 metres Wire/cables at 7.0 metres Refusal terminated on account of steel cable/wire D1MW5_6.0-7.0 D1MW5_7.0-7.2			FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay	D1MW5_2.0-3.0			•		
FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay, with waste Water at 5.8 metres Wire/cables at 7.0 metres Refusal terminated on account of steel cable/wire D1MW5_6.0-7.0 D1MW5_7.0-7.2	- Auger			D1MW5_3.0-4.0					
waste Water at 5.8 metres Wire/cables at 7.0 metres Refusal terminated on account of steel cable/wire D1MW5_6.0-7.0 D1MW5_7.0-7.2									
Refusal terminated on account of steel cable/wire D1MW5_6.0-7.0 D1MW5_7.0-7.2	- I I I		waste Water at 5.8 metres	D1MW5_5.0-6.0					
				D1MW5_6.0-7.0					
	· -			D1MW5_7.0-7.2					

Drill Company: SDI

Date Commenced:

Drill Model: Date Completed: 15/10/15

Hole Diameter (mm): Logged/checked by: EM/JD

Sheet: 1 of 1

15/10/15

Boyd Properties Pty Ltd

Easting: Northing: CONSULTING SCIENTIS TS

Project: CES130806-BP

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Client:

Environmental Log:

D1MW5b

DRILLING INFO.	LITHOLOGY	SAMPLING INFORMATION	
Depth Method Water	Symbol Description	PID (ppm) Sample ID Type O O O	Well Construction
0	FILL: Clayey SAND: brown, fine, dry - with low to medium plasticity clay, and with fragments of brick Steel around 1.7 metres	D1MW5b_0.0-1.0	
1		D1MW5b_1.0-2.0	
2-			
3—			
4_			

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 15/10/15

Date Completed: 15/10/15

Logged/checked by: EM/JD

Project: CES130806-BP

Northing:

Easting:

EARTH SCIENTISTS

g.

Client: Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1MW6

DRILLING INFO.		LITHOLOGY	SAMPL	ING IN	FORMATION	
Depth Method Wate	Symbol	Description	Sample ID	Туре	PID (ppm) 0 22 09	Well Construction
0		FILL: Capping Layer Gravelly SAND: brown, fine, dry	D1MW6_0.0-1.0		•	
1-		FILL: Clayey SAND: dark brown, fine, dry, with high plasticity clay, with waste (treated wood), and moderate hydrocarbon odour Becoming moist around 3.0 metres	D1MW6_1.0-2.0		•	
2-		Presence of nylon fishing line - new V bit. Wet at 4.5 metres	D1MW6_2.0-3.0			
3 -			D1MW6_3.0-4.0		•	
4-	•		D1MW6_4.0-5.0		•	
5			D1MW6_5.0-6.0		•	
6-			D1MW6_6.0-7.0		•	
7						
8-						

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 15/10/15

Date Completed: 15/10/15

Logged/checked by: EM/JD

Project: **Environmental Site Assessment** Northing:


CONSULTING IENTIS TS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Boyd Properties Pty Ltd Client:

Elevation:

D1MW7



Site Drilling and Investigations **Drill Company:**

Drill Model: EDSON 100

Hole Diameter (mm): N/A **Date Commenced:** 16 October 2015

Date Completed: 16 October 2015

Logged/checked by: WS

Project: Environmental Site Assessment


Northing:

CONSULTING EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:



Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 16 October 2015

Date Completed: 16 October 2015

Logged/checked by: WS

Client: Boyd Properties Pty Ltd
Project: Cooks Cove Development

CONSULTING EARTH SCIENTISTS Level 1, 55 Grandview Street

Suite 3, Pymble, NSW 2073 PH: (02) 8569 2200 FAX: (02) 9552 4399 www.consultingearth.com.au Borehole No: D1G01

for details of abbreviations

Sheet: 1 of 2

Location: Area D1, Cooks Cove

Machine Type: Edson 100 (Truck mounted)

X-Coord: 329417.8 **Y-Coord:** 6242098.2

Date Commenced: 22/10/2015 **Date Completed:** 23/10/2015 Logged by: M.E Checked by: S.M

Surface Elevation (R.L): 4.51 m AHD Hole Diameter (mm): 125

illing	Inform	ation			LITHOLOGY			Samples	Tests		
R.L. (m)	Method (Support)	Water	Symbol	USCS Symbol	Description SOIL TYPE: plasticity or particle characteristics colour, moisture, secondary and minor component	Consistency / Density	Moisture	Sample ID	SPT	Pocket 200 Penetrometer 300 (kPa)	Notes and additional observations
					TOPSOIL: Silty Sand, dark brown, fine to medium grained, trace fine to medium gravel and ash. FILL: Sand, black and dark grey, fine to medium grained, fine to medium gravel of shale, sandstone and aggregate with minor clay content. Ash, glass, wire, plastic, broken concrete and wood fragments throughout.	L	D M		SPT01 1.5- 1.95m 6, 8, 4 N =12		
	——————————————————————————————————————	ightharpoons			At 4.0m, increasing in wood fragments, wire and clay content.		W		SPT02 3.0m N>10 Refusal, bouncing on 0.5 inch wire. SPT03 4.5-4.95m 6, 2, 6 N = 8		
					6.2m SAND: Light grey and dark grey, fine to medium grained, shells throughout. (Alluvium)	VL - MD	W		SPT04 6.0- 6.45m 2, 2, 3 N = 5		
-3	<u></u>	-							SPT05 8.25- 8.70m 4, 5, 7 N=12		
-4					In SPT05 8.25-8.70m, large amount of shell fragments.				SPT06 9.75- 10.20m N = 0 dropped		
					At 9.75m, minor clay content.				under weight of hammer	-	

Client: Boyd Properties Pty Ltd
Project: Cooks Cove Development

6242098.2

Area D1, Cooks Cove

CONSULTING EARTH SCIENTISTS Level 1, 55 Grandview Street

Suite 3, Pymble, NSW 2073 PH: (02) 8569 2200 FAX: (02) 9552 4399 www.consultingearth.com.au Borehole No: D1G01

Sheet: 2 of 2

X-Coord: 329417.8

Location:

Y-Coord:

Date Commenced:22/10/2015Logged by:M.EDate Completed:23/10/2015Checked by:S.M

Surface Elevation (R.L): 4.51

m AHD **Hole Diameter (mm):** 125

)rill	ing In	form	ation			LITHOLOGY			Samples	Tests		
Depth (mBGL)	R.L. (m)	Method (Support)	Water	Symbol	USCS Symbol	Description SOIL TYPE: plasticity or particle characteristics colour, moisture, secondary and minor component	Consistency / Density	Moisture	Sample ID	SPT	Pocket 200 Penetrometer 300 (kPa)	Notes and additional observations
1 -	-6 7					SAND (Continued): Light grey and dark grey, fine to medium grained, shells throughout. (Alluvium) 11.5m	VL - MD	w		SPT07 11.25- 11.70m 2,1,1		1
2-	—-8					SAND: Grey and light grey, fine to medium grained, very stiff medium to high plasticity sandy clay bands throughout. Trace shells. (Alluvium)	MD	M-W		N = 2		1
3	— -9									SPT08 12.75- 13.05m 15,25 N>25		1
	10	Wash Bore (MUD)								SPT09 14.25- 14.52m 21,25 N>25		1
	— -11									SPT10 15.75-		1
111111111	— -12									16.20m 8,8,11 N = 19		1
	— -13					At 17.0m, becoming dark grey.				SPT11 17.25- 17.70m 9,9,10 N = 19		1
1111111	— -14					18.5m Clayey SAND: Light grey to white	MD-D	M		SPT12 18.75- 19.20m 7,17, 24 N = 41		1
111111111	— -15					and brown, low plasticity, fine to medium sand, medium to coarse gravel of sandstone.(Residual soil)						1
11111111	— -16					At 20.5m losing water flush. Approximately 40% returns. Refusal of bit at 20.8m, refer to cored borehole log.				SPT13 20.25- 20.7m 7,11,14 N = 25		2

Drill Company: Site Drilling and Investigation **Machine Type:** Edson 100 (Truck mounted)

Operator Name:

Doug Millar

Refer to Standard Sheets for details of abbreviations

Client: Boyd Properties Pty Ltd
Project: Cooks Cove Development

Area D1, Cooks Cove



Level 1 55 Grandview Street Suite 3, Pymble, NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582 www.consultingearth.com.au

Corehole No: D1G01

for details of abbreviations

Sheet: 1 of 2

X-Coord: 329417.8 **Y-Coord:** 6242098.2

Location:

Machine Type:


Edson 100 (Truck mounted)

 Date Commenced:
 22/10/2015

 Date Completed:
 23/10/2015

Logged by: M.E **Checked by:** S.M

Surface Elevation (R.L): 4.51 Hole Diameter (mm): 51.95



Client: Boyd Properties Pty Ltd
Project: Cooks Cove Development
Location: Area D1, Cooks Cove



Level 1 55 Grandview Street
Suite 3, Pymble, NSW 2073
PH: (02) 8569 2200 FAX: (02) 9983 0582
www.consultingearth.com.au

Corehole No: D1G01


Sheet: 2 of 2

X-Coord: 329417.8 **Y-Coord:** 6242098.2
 Date Commenced:
 22/10/2015

 Date Completed:
 23/10/2015

Logged by: M.E **Checked by:** S.M

Surface Elevation (R.L): 4.51 Hole Diameter (mm): 51.95



Groundwater Monitoring Well Installation

Gatic Cover at the surface. Casing: 0.0 - 2.0m Screen: 2.0 - 6.0m Concrete: 0.0 - 0.2m Bentonite Plug: 0.2 - 1.2m Sand Filter: 1.2 - 7.0m Bentonite Plug: 7.0 - 8.5m

Sand Backfill: 8.5 - 28.26m (E.O.H)

Drill Company: Site Drilling and Investigation **Machine Type:** Edson 100 (Truck mounted)

Operator Name: Doug Millar

Refer to Standard Sheets for details of abbreviations





Client: Boyd Properties Pty LtdProject: Cooks Cove DevelopmentLocation: Area D1, Cooks Cove

6242115.8

Machine Type: Edson 100 (Truck mounted)

CONSULTING EARTH SCIENTISTS Level 1, 55 Grandview Street

Suite 3, Pymble, NSW 2073 PH: (02) 8569 2200 FAX: (02) 9552 4399 www.consultingearth.com.au Borehole No: D1G02

for details of abbreviations

Sheet: 1 of 2

X-Coord: 329388.7

Y-Coord:

Date Commenced: 20/10/2015 **Date Completed:** 21/10/2015 **Logged by:** M.E Checked by: S.M

Surface Elevation (R.L): 4.65

m AHD **Hole Diameter (mm):** 125

rillin	ıg In	form	ation			LITHOLOGY			Samples	Tests		
	R.L. (m)	Method (Support)	Water	Symbol	USCS Symbol	Description SOIL TYPE: plasticity or particle characteristics colour, moisture, secondary and minor component	Consistency / Density	Moisture	Sample ID	SPT	Pocket 200 Penetrometer 300 (kPa)	Notes and additional observations
	3 3 - 2 - 2	ADV ————————————————————————————————————	∇			TOPSOIL: Silty Sand, grey and brown, fine to medium grained, trace fine to coarse gravel. Roots and wood fragments. FILL: Clayey Sand, black and brown, fine to medium grained, low plasticity, trace fine to medium gravel of sandstone and roadbase. Plastic, wood, brick fragments, glass shards.	L VL - L	D M		SPT01 1.5- 1.95m 1, 4, 11 N >15 Bouncing on wood. SPT02 3.0- 3.375m 4, 3, 7 N>10 Bouncing on wood. SPT03 4.5- 4.95m 3, 2, 3 N = 5		
	· -1					7.5m				SPT04 6.0- 6.45m 6, 13, 5 N > 18 Bouncing on wood and wire.		
	3					Sandy CLAY: Black, medium to high plasticity, fine to medium sand with trace shells. (Alluvium)	S - F	M		SPT05 7.5- 7.95m 1, 2, 2 N = 4		
	·-5					9.0m Clayey SAND: Grey, fine to medium grained, low plasticity. (Alluvium)	VL	W		SPT06 9.0- 9.45m N = 0 Dropped under weight of hammer		
	-5									SPT07 10.0- 10.45m 2, 1, 1 N = 2		

Client: Boyd Properties Pty Ltd
Project: Cooks Cove Development
Location: Area D1, Cooks Cove

CONSULTING EARTH SCIENTISTS Level 1, 55 Grandview Street

Suite 3, Pymble, NSW 2073 PH: (02) 8569 2200 FAX: (02) 9552 4399 www.consultingearth.com.au Borehole No: D1G02

Sheet: 2 of 2

Location: Area D1, Cooks C
X-Coord: 329388.7

X-Coord: 329388.7 **Date Commenced:** 20/10/2015 **Logged by:** M.E **Y-Coord:** 6242115.8 **Date Completed:** 21/10/2015 **Checked by:** S.M

Surface Elevation (R.L): 4.65 m AHD Hole Diameter (mm): 125

Drill	ing In	form	ation			LITHOLOGY			Samples	Tests		
Depth (mBGL)	R.L. (m)	Method (Support)	Water	Symbol	USCS Symbol	Description SOIL TYPE: plasticity or particle characteristics colour, moisture, secondary and minor component	Consistency / Density	Moisture	Sample ID	SPT	Pocket 200 Penetrometer 300 (kPa)	Notes and additional observations
11	—-6			· · ·		Clayey SAND (Continued): Grey, fine to medium grained, low plasticity. (Alluvium)	VL	W				11 -
12		(MUD)								SPT08 11.5- 11.95m 2, 1, 2 N = 3		12 -
13 -	8	— Water Bore (MUD)				13.5m				SPT09 13.0- 13.45m 9, 14, 9 N = 23		13 -
14 -	- -9					CLAY: Light brown and grey, high plasticity, trace fine sand. (Residual soil)	St - V St	М				14 -
15 —	10					Sandy CLAY/Clayey SAND: Grey and light brown, fine to medium sand, low to medium plasticity. (Residual soil)	D & H	M		SPT10 14.5- 14.95m 11, 14, 17 N = 31		15-
16 -										SPT11 16.0- 16.45m 5, 11, 24 N = 35		16 -
17 — - - - -	⊢ -12 ⊢ ₋₁₃					Refusal of bit at 17.7m, refer to cored borehole log.				SPT12 17.5- 17.385m 4, 7, 17 N > 24 Bouncing on bedrock.		17 -

Drill Company: Site Drilling and Investigation **Machine Type:** Edson 100 (Truck mounted)

Operator Name: D

Doug Millar

Refer to Standard Sheets for details of abbreviations

Client: Boyd Properties Pty Ltd
Project: Cooks Cove Development
Location: Area D1, Cooks Cove



Level 1 55 Grandview Street
Suite 3, Pymble, NSW 2073
PH: (02) 8569 2200 FAX: (02) 9983 0582
www.consultingearth.com.au

Corehole No: D1G02

Sheet: 1 of 1

X-Coord: 329388.7 **Y-Coord:** 6242115.8


 Date Commenced:
 20/10/2015

 Date Completed:
 21/10/2015

Logged by: M.E **Checked by:** S.M

Surface Elevation (R.L): 4.65

Hole Diameter (mm): 51.95



Groundwater Monitoring Well Installation

Gatic Cover at the surface. Casing: 0.0 - 2.0m Screen: 2.0 - 6.0m Concrete: 0.0 - 0.2m Sand Backfill: 0.2 - 0.5m Bentonite Plug: 0.5 - 1.5m Sand Filter: 1.5 - 8.0m Bentonite Plug: 8.0 - 9.5m

Sand Backfill: 9.5 - 19.96m (E.O.H)

Drill Company: Site Drilling and Investigation **Machine Type:** Edson 100 (Truck mounted)

Operator Name: Doug Millar

Refer to Standard Sheets for details of abbreviations



Project: Environmental Site Assessment

Northing:

SCIENTISTS


Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

CONSULTING

Client: Boyd Properties Pty Ltd

Elevation:

Cove Day Environmental Lagy D1DU10



Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 16 October 2015

Date Completed: 16 October 2015

Logged/checked by: WS

CES130806-BP

Boyd Properties Pty Ltd

Easting: Northing: CONSULTING SCIENTIS TS

Project:

Client:

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove **Environmental Log: D1BH11**

DRILLING INFO.		LITHOLOGY	SAMPI			
Depth Method Water	Symbol	Description	Sample ID	Туре	PID (ppm) 0 220 220 0 02	Well Construction
1-		FILL: SAND: brown, fine to medium, dry	D1BH11_0-1.0			
- Auger		FILL: Clayey SAND: dark brown, fine to medium, most, with treated wood	D1BH11_1.3-1.7		•	
		FILL: Clayey SAND: brown to grey, medium, moist	D1BH11_1.7-2.0		•	
2-		FILL: Clayey SAND: dark brown, medium to fine, moist, with waste (treated timber)	D1BH11_2.0-3.0			
4-						

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 13/10/15

Date Completed: 13/10/15

Logged/checked by: EM/JD

050400000000

Boyd Properties Pty Ltd

Northing:

Easting:

EARTH SCIENTISTS

Project: CES130806-BP

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Client:

Environmental Log:

D1BH12

Depth Method Water Symbol Description Sample ID Type PID (ppm) PiD (ppm) Well Constitution PiD (ppm) PiD			ΓΙΟΝ	RMA	NG INFO	SAMPL	LITHOLOGY		INFO.	DRILLING
FILL: Capping Layer Gravelly SAND: grey to brown, medium, dry, with bricks FILL: Clayey SAND: brown, fine, dry - with high plasticity clay, with glass waste FILL: Clayey SAND: dark brown, medium, dry - with high plasticity clay, waste (mattress) D1BH12_0.4-1.0 D1BH12_1.1-2.0 D1BH12_1.1-2.0	Well Construct	0			Type ,	Sample ID	Description	Symbol	d Water	Depth Method
FILL: Clayey SAND: dark brown, medium, dry - with high plasticity clay, waste (mattress) D1BH12_1.1-2.0 D1BH12_2.0-3.0			20	52						
medium, dry - with high plasticity clay, waste (mattress) D1BH12_2.0-3.0						D1BH12_0.4-1.0	FILL: Clayey SAND: brown, fine, dry - with high plasticity clay, with glass waste			- - - - -
D1BH12_2.0-3.0				•		D1BH12_1.1-2.0	FILL: Clayey SAND: dark brown, medium, dry - with high plasticity clay, waste (mattress)		Jagar Vage	1-
3			*			D1BH12_2.0-3.0				2 —
										- - - - - - - -

Drill Company: SDI

. ,

Hole Diameter (mm):

Drill Model:

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

CES130806-BP

Easting:
Northing:

EARTH SCIENTISTS

Client: Bo

Project:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH13

DRILLING INFO.		LITHOLOGY	SAMP	LING IN	IFORMATION	
Depth Method Water	Symbol	Description	Sample ID	Туре	PID (ppm) 0 052 05	Well Construction
0		FILL: Gravelly/Clayey SAND: brown, medium, dry - with high plasticity clay, and with angular gravel	D1BH13_0-1.0			
1-			D1BH13_1.0-1.4		•	
Auger		FILL: Clayey SAND: dark brown, fine to medium, dry- with high plasticity clay	D1BH13_1.4-1.8		•	
2-		FILL: Clayey SAND: fine to medium, with timber - peat	D1BH13_1.8-2.0			
			D1BH13_2.4-3.0			
3						
4-						
5_						

Drill Company: SDI

. ,

Hole Diameter (mm):

Drill Model:

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH14

DRILLING IN	FO.		LITHOLOGY	SAMPI	LING INFO	RMATION	
Depth Method	Water	Symbol	Description	Sample ID	Туре с	FID/PID (ppm)	WELL DETAIL
0-,							
1			FILL: Silty sand, fine, grey, dry becoming grey to dark brown with gravels	D1BH14_0-1.0 D1BH14_1.0-1.5			
2 —				D1BH14_1.5-2.0 D1BH14_2.0-2.4			
			Refusal at 2.4 mbgl				
3			renada at 2.7 magi				

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 12/10/2015

Date Completed: 12/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH15

DRILLING IN	IFO.		LITHOLOGY	SAMP	LING IN	FORM	IATI	ON		
Depth Method	Water	Symbol	Description	Sample ID	Туре	F	ID/PII	O (ppr	n)	WELL DETAIL
			1		71		250	200	09/	
			FILL: sand, brown, fine, dry with traces of clay and presence of bricks	D1BH15_0-1.0		•				
1			FILL: sandy clay, brown, medium plasticity, dry with fine sand and fragments of bricks	D1BH15_1.0-1.5		•				
2 —				D1BH15_2.0-3.0		*				
3										

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 12/10/2015

Date Completed: 12/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH16

DRILLING II	NFO.		LITHOLOGY	SAMP	LING IN	IFORMATION	
Depth Method	Water	Symbol	Description	Sample ID	Туре	FID/PID (ppm)	WELL DETAIL
					71-	255 500 500 755	
			FILL: sand, brown, fine, dry with traces of plastic waste	D1BH16_0-1.0			
1				D1BH16_1.0-2.0		•	
2-			FILL: ash, grey, fine, dry Refusal at 2.2 mbgl	D1BH16_2.0-2.2		•	
3							

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 12/10/2015

Date Completed: 12/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Cooks Cove

Location:

Elevation:

Environmental Log: D1BH17

DRIL	LING INFO		LITHOLOGY	SAMP	LING IN	IFORMA	TION	
Donth I	Method Wat	or Symbol	Description	Sample ID	Typo	FID	PID (ppm)	WELL DETAIL
Берин	wiethod wa	er Symbol	Description	Sample ID	Туре	0 250	500	
0-								71
- - - - -	— Auger		FILL: gravelly sand, dark brown, fine, dry with angular gravels and presence of rubbles and metallic waste	D1BH17_0-0.5		+		
1	\							
. '			Refusal at 1.0 mbgl					
2 —								
3								

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 12/10/2015

Date Completed: 12/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH18

DRILLING INFO.		LITHOLOGY	SAMPI	ING IN	FORMATION	
Depth Method Water	Symbol	Description	Sample ID	Туре	FID/PID (ppm) 0 220 220 0 220 420	WELL DETAIL
0-,				¬.		1
Auger —		FILL: silty sand, grey to dark brown, fine, dry	D1BH18_0-1.0		**	
1-		FILL: sand, gry, fine, dry	D1BH18_1.0-1.1			
2 —						
3						

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 12/10/2015

Date Completed: 12/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH19

DRILLING IN	FO.		LITHOLOGY	SAMP	LING IN	FORI	MAT	ION	
Depth Method	Water	Symbol	Description	Sample ID	Туре	• F	520 P	ID (ppm)	WELL DETAIL
0			FILL: silty sand, dark brown, fine, dry with bricks fragments and plastic waste	D1BH19_0-0.5		•			
				D1BH19_0.5-1.0		•			
1 - Auger				D1BH19_1.5-2.0		•			
- - - - -			becoming gravelly sand						
2			Refusal at 2.0 mbgl						
3			Nerusai at 2.0 mbgi						

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 12/10/2015

Date Completed: 12/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH20

DRILLING IN	IFO.		LITHOLOGY	SAMP	LING IN	FORM	IATION	
Depth Method		Symbol	Description	Sample ID	Туре		D/PID (ppm) 200 200 200 200 200 200 200 200 200 200	WELL DETAIL
							<u> </u>	
0-			FILL: sand, dark brown, fine, dry	D1BH20_0-0.4		•		
1 - Auger			FILL: clayey sand, fine to medium, brown, dry with low to medium plasticity clay and brick fragments	D1BH20_0.4-1.5		•		
2 -				D1BH20_2-3		•		
3			Refusal at 3.0 mbgl					

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 13/10/2015

Date Completed: 13/10/2015

Logged/checked by: GH/JD

Project: CES130806-BP Northing:



Suite 3, Level 1 55 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

Location: Cooks Cove Environmental Log: D1BH21

DRILLING INF	о.	LITHOLOGY	SAMPL	ING IN	FORMAT	ION	
Depth Method W	/ater Symbo	Description	Sample ID	Туре	0 550 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	PID (ppm)	WELL DETAIL
0-,				¬.			
1-		FILL: silty sand, dark brown, fine, dry with bricks fragments, plastic and timber waste and gravels	D1BH21_0-1.0				
- Auger		presence of fragments of wood with strong hydrocarbon odour	D1BH21_1.5-2.5				
3		presence of ash	D1BH21_2.5-3.0		•		

Drill Company: SDI **Date Commenced:** 12/10/2015

Drill Model: Date Completed: 12/10/2015

Hole Diameter (mm): Logged/checked by: GH/JD

CES130806-BP

Northing:

Easting:

CONSULTING EARTH SCIENTISTS

Project: CES130

Client:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH22

DRILLING INFO.	Lľ	THOLOGY	SAMPI	LING INI	FORMATION	
Depth Method Water		Description	Sample ID	Туре	PID (ppm) 0 09 09 09 09 09 09 09 09 09 09 09 09 09	Well Construction
0	FILL: SANI bricks fragi	D: brown, medium, dry with ments	D1BH22_0-1.0		22 25 26 27	
1	FILL: Claye dry, mediui gravels	ey SAND: brown, medium, m plasticity, with bricks and	D1BH22_1-2		•	
2-			D1BH22_2-3			
3 — — — — — — — — — — — — — — — — — — —						

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 13/10/15

Date Completed: 13/10/15

Logged/checked by: EM/JD

Project: Environmental Site Assessment

Northing:


CONSULTING EARTH SCIENTISTS

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Client: Boyd Properties Pty Ltd

Elevation:

.... D4D1100



Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 16 October 2015

Date Completed: 16 October 2015

Logged/checked by: WS

CES130806-BP

Easting: Northing:

EARTH SCIENTISTS

Project: Client:

Boyd Properties Pty Ltd


Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Environmental Log:

D1BH24



Drill Company: SDI

. ,

Hole Diameter (mm):

Drill Model:

Date Commenced: 13/10/15

Date Completed: 13/10/15

Logged/checked by: EM/JD

Boyd Properties Pty Ltd

Easting: **Northing:** CONSULTING CIENTISTS

Project: CES130806-BP

Elevation:


Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Cooks Cove Location:

Client:

Environmental Log:

D1BH25



Drill Company: SDI

Date Commenced:

Drill Model: Date Completed: 14/10/15

Hole Diameter (mm): Logged/checked by: EM/JD

Sheet: 1 of 1

14/10/15

CES130806-BP

Easting:

EARTH SCIENTISTS

Northing:

Client:

Project:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH26

					DIDIIZO	
DRILLING INFO.		LITHOLOGY	SAMPL	ING IN	FORMATION	Well Construction
Depth Method Water	Symbol	Description	Sample ID	Туре	PID (ppm) 0 250 0 250	Someti detion
0	FILL: 0 moist,	Gravelly SAND: dark brown, fine, angular gravel	D1BH23_0.0-1.0			
1- Jage 1 Jage 1	KXXXXI	Clayey SAND: dark brown, fine dium,moist, with timber and waste, high hydrocarbon odour ning wet at 1.8 metres	D1BH26_1.3-2.0			
3			D1BH26_2.0-3.0			
4 —						

Drill Company: SDI

OD

Drill Model:

Hole Diameter (mm):

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

CES130806-BP

Easting:
Northing:

EARTH SCIENTISTS

Project: CES1:

Client:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH27

DRILLING INFO.	LITHOLOGY	SAMP	LING INFORMATION	
Depth Method Water	Symbol Description	Sample ID	PID (ppm) Type 0 092	Well Construction
1-	Topsoil FILL: Gravelly SAND: brown medium, dry, with brick and a gravels	fine to angular		
2-	FILL: SAND: dark brown, fine medium, dry FILL: SAND: dark brown, fine	D1BH27_2.0-3.0		
3	medium, dry, with treated wo	od.	•	
4-				
5_				

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 13/10/15

Date Completed: 13/10/15

Logged/checked by: EM/JD

Environmental Site Assessment

Northing:

Easting:

SCIENTIS TS
Suite 3, Level 1

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582


CONSULTING

Client: Boyd Properties Pty Ltd

Project:

Elevation:

Location: Bestic St, Banksia - Cook Cove Dev. Environmental Log: D1BH28



Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 16 October 2015

Date Completed: 16 October 2015

Logged/checked by: WS

Sheet: 1/1

Project:

Client:

CES130806-BP

Boyd Properties Pty Ltd

Easting:

CONSULTING SCIENTIS TS

Northing:

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove **Environmental Log: D1BH29**

DRILLING INFO.	LITHOLOGY Symbol Description		SAMPL					
Someth Markhard Marks			Commis ID	T		(ppm)		Well Construction
Depth Method Wate	Symbol	Description	Sample ID	Туре	0	200	750	
		FILL: Gravelly SAND: brown, fine to medium, dry, with rubble Becomiing dark brown with hydrocarbon odour	D1BH29_0.0-1.0B					
1-			D1BH29_0.0-1.0	/				
Auger —		FILL: SAND: dark brown, moist, with hydrocarbon odour	D1BH29_1.6-2.0					
2-		FILL: SAND: with waste	D1BH29_2.4-3.0					
3								

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 13/10/15

Date Completed: 13/10/15

Logged/checked by: EM/JD

Boyd Properties Pty Ltd

Northing:

Easting:

CONSULTING SCIENTIS TS

Project: CES130806-BP

Client:

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove **Environmental Log: D1BH30**

DRILLING INFO.		LITHOLOGY	SAMPI	LING IN	IFORMATION	
Depth Method Wate	Symbol	Description	Sample ID	Туре	PID (ppm) 0 022 09 220 09	Well Construction
0		FILL: Gravelly SAND: dark brown, fine to medium, dry	D1BH30_0-1.0			
2-		FILL: Clayey SAND: dark brown, medium, moist, medium plasticity, with timber, plastic, glass, and ash, high hydrocarbon odour FILL: Clayey SAND: with treated timber FILL: CLAY: grey, dry to moist, high plasticity, with waste (glass, gravel)	D1BH30_1.6-2.0 D1BH30_2.0-2.5			
4- - - - - - - - - - - - - - - - - - -			D1BH30_2.5-3.0			

Drill Company: SDI **Date Commenced:**

Drill Model:

Date Completed: 13/10/15

Hole Diameter (mm):

Logged/checked by: EM/JD

Sheet: 1 of 1

13/10/15

CES130806-BP

Northing:

Easting:

EARTH SCIENTISTS

Project:

Client:

CE3130000-DI

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH31

DRILLING INFO.	LITHOLOGY	SAMPI	LING INFORMATION	
Depth Method Water	Symbol Description	Sample ID	PID (ppm) Type	Well Construction
Depth Method Water 0	FILL: Gravelly SAND: brown medium, dry FILL: Clayey SAND: dark boto medium, moist with high clay, waste (wood, plastic), hydrocarbon odour Silty SAND: dark brown, fin medium, wet, moderate hydrodour	rown, fine plasticity strong D1BH31_1.0-2.0B D1BH31_1.0-2.0 D1BH31_2.2-3.0	25 25 25 25 25 25 25 25 25 25 25 25 25 2	
3	Possible natural material			

Drill Company: SDI

•

Hole Diameter (mm):

Drill Model:

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

Boyd Properties Pty Ltd

Northing:

CONSULTING SCIENTIS TS

Project: CES130806-BP

Elevation:

Easting:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Client:

Environmental Log:

D1BH32

DRILLING INF	o.	LITHOLOGY	SAMPL	ING IN	FOR	MA	TION		
D			Sample ID Type			PID	(ppm)	Well Construction	
Depth Method W	ater Symbol	Description	Sample ID	Туре	0	250	200	750	
		FILL: Gravelly SAND: grey, fine to medium, dry, subangular-angular gravels	D1BH32_0-1.0						
		FILL: Clayey SAND: dark brown, fine to medium, dry, gravelly with brick	D1BH32_1.2-2.0						
2-		FILL: Clayey SAND: dark brown, fine to medium, moist, with waste (plastic, treated wood), hydrocarbon odour	D1BH32_2.4-3.0					•	
3									
5_									

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced:

13/10/15

Date Completed:

13/10/15

Logged/checked by:

EM/JD

Easting: Northing: CONSULTING SCIENTIS TS

Project: CES130806-BP

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Client:

Environmental Log:

D1BH33

DRILLING INFO		LITHOLOGY	SAMPL					
Depth Method Wa	or Symbol	Description	Sample ID	Туре		ID (ppn		Well Construction
0		FILL: Gravelly SAND: brown, medium, dry, with angular gravel	D1BH33_0-1.0		0	250	750	
1-								
-		FILL: Clayey SAND: dark brown, fine, moist - with high plasticity clay, with waste (plastic, brick and mattress), hydrocarbon odour Becoming Sandy CLAY at approximately 2.8 metres	D1BH33_1.3-2.0B					
			D1BH33_1.3-2.0 D1BH33_2.0-3.0			•	•	
3								
5								

Drill Company: SDI

Hole Diameter (mm):

Drill Model:

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

Boyd Properties Pty Ltd

Easting:

Elevation:

CONSULTING SCIENTIS TS

Project: CES130806-BP

Client:

Northing:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove **Environmental Log:**

D1BH34

DRILLING I	NFO.		LITHOLOGY	SAMPI	ING IN	IFORMATION	
Depth Method	Water	Symbol	Description	Sample ID	Туре	PID (ppm) 0 022 220 0 094	Well Construction
0			FILL: Gravelly SAND:brown, medium, dry, angular gravel	D1BH34_0-1.0			
1-				D1BH34_1.0-1.7			
-			FILL: Clayey SAND: dark brown, fine, moist, medium plasticiity, with timber, with trace of coal/coke (black shiny	D1BH34_1.7-2.0		*	
3			element)	D1BH34_2.0-3.0		•	
4-							
5_							

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

Boyd Properties Pty Ltd

Easting:

CONSULTING SCIENTIS TS

Project: CES130806-BP Northing:

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Client:

Environmental Log:

D1BH36

DRILLING INFO.		LITHOLOGY	SAMPL	ING IN	FOR	MΑ	TION		
Depth Method Water	r Symbol Description		Sample ID	Туре	PID (ppm)				Well Construction
0		FILL: Gravelly SAND: brown, fine to medium, dry	D1BH36_0-1.5			250	200	220	
7									
		FILL: Clayey SAND: dark brown, medium, dry, clay is medium plasticity, with waste	D1BH36_1.7-2.0			•			
2-			D1BH36_2.0-2.3			•			
3-									
4									

Drill Company: SDI

Hole Diameter (mm):

Drill Model:

Date Commenced: 13/10/15

Date Completed: 13/10/15

Logged/checked by: EM/JD

Project ID: CES130608-BP Easting:

Project: Environmental Site Assessment

Northing:

SCIENTISTS


Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

CONSULTING

Client: Boyd Properties Pty Ltd

Elevation:

Location: Bestic St, Banksia - Cook Cove Dev. Environmental Log: D1BH37



Drill Company: Site Drilling and Investigations

Drill Model: EDSON 100

Hole Diameter (mm): N/A

Date Commenced: 16 October 2015

Date Completed: 16 October 2015

Logged/checked by: WS

Sheet: 1/1

CES130806-BP

Easting:
Northing:

EARTH SCIENTISTS

Project:
Client:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Environmental Log:

D1BH39

DRILLING INFO.		LITHOLOGY	SAMPL	ING IN	IFORM.	ATIO	N	
Depth Method Water	r Symbol	Description	Sample ID	Туре	PII O	O (ppn		Well Construction
1-		FILL: Gravelly SAND:brown, fine to medium, dry, angular gravel	D1BH39_0-1.0		•			
2-		FILL: SAND: dark brown, medium, moist, with wood waste, moderate hydrocarbon odour	D1BH39_1.8-2.0 D1BH39_2.0-2.4				•	
3		FILL: Gravelly SAND: brown, medium, dry, subangular to angular gravel and rubble, strong hydrocarbon odour	D1BH39_2.4-3.0				•	
4-								
5_								

Drill Company: SDI

Date Commenced: 13/10/15

Drill Model:

Date Completed: 13/10/15

Hole Diameter (mm):

Logged/checked by: EM/JD

Project:

CES130806-BP

Northing:

Elevation:

Easting:

CONSULTING SCIENTIS TS

Client: Boyd Properties Pty Ltd

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove **Environmental Log: D1BH41**

DRILLING INFO.		LITHOLOGY	SAMPL	ING IN	FORMAT	ION	
Depth Method Water	Symbol	Description	Sample ID	Туре	PID (ppm)	Well Construction
0		FILL: Clayey SAND: brown to dark brown, fine to medium, dry with high plasticity, clay with traces of waste (plastic, wood)	D1BH41_0-0.6		55	20 20 20 20 20 20 20 20 20 20 20 20 20 2	
1-	F	FILL: Sandy CLAY: dark brown, medium, moist, high plasticiity, with trace of waste (wood), moderate to high hydrocarbon odour	D1BH41_0.6-1.0				
- Jaban Japan Ja			D1BH41_1.0-2.0			•	
	V (FILL: Sandy CLAY: dark brown, fine to medium, moist with high plasticity, no waste, low hydrocabon odour Possible natural material	D1BH41_2.1-3.0		*		
4-							
5_							

Drill Company: SDI

Date Commenced: 14/10/15

Drill Model:

Date Completed: 14/10/15

Hole Diameter (mm):

Logged/checked by: EM/JD

Project:

Client:

CES130806-BP

Northing:

Easting:

EARTH SCIENTISTS

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH42

DRILLING INFO.	LITHOLOGY	SAMPLING	INFORMATION	
Depth Method Water	Symbol Description	Sample ID Typ	PID (ppm) e o o o	Well Construction
0	FILL: Gravelly SAND: brown , fine, dry, with subangular to angular gravel	<u> </u>	\$ 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
2- -	FILL: Clayey SAND: dark brown, fine to medium, dry, angular gravel, with rubble, pastic, wood, concrete, strong hydrocarbon odour	D1BH42_1.0-2.0B D1BH42_1.0-2.0 D1BH42_2.0-3.0		
4				

Drill Company: SDI

Drill Model:

Hole Diameter (mm):

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

CES130806-BP

Easting:
Northing:

EARTH SCIENTISTS

Project:

Client:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH43

DRILLING INFO.		LITHOLOGY	SAMPL	ING IN	FORMATION	
Depth Method Water	Symbol	Description	Sample ID	Туре	PID (ppm)	Well Construction
0			D1BH43_0-1.0]	250 0 250 0 750 1	
- - - - - - - - - - - - - - - - - - -	FI	LL: Gravelly SAND: pale brown and ey, medium to coarse, moist, with agular gravel LL: CLAY: dark brown, medium, poist, high plasticity			•	
2-		et at 1.2 metres	D1BH43_1.3-2.0B			
3						
4-						
5_						

Drill Company: SDI

. ,

Hole Diameter (mm):

Drill Model:

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

Project:

Client:

CES130806-BP

Northing:

Easting:

EARTH SCIENTISTS

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove

Environmental Log: D1BH44

DRILLING INFO.	LITHOLOGY	SAMPL	SAMPLING INFORMATION							
Depth Method Water	Symbol Description	Sample ID	Туре	PID (ppm)	Well Construction					
	оунный везоприон	Gample 15	Турс	250						
0	FILL: Gravelly SAND: brown , fine to medium, dry	D1BH44_0-0.2		•						
	FILL: SAND: grey, fine, dry, hard	D1BH44_0.2-0.9								
1-										

Drill Company: SDI

. ,

Hole Diameter (mm):

Drill Model:

Date Commenced: 14/10/15

Date Completed: 14/10/15

Logged/checked by: EM/JD

CES130806-BP

Easting:
Northing:

EARTH SCIENTISTS

Project:

Client:

Boyd Properties Pty Ltd

Elevation:

Suite 3, Level 1 55-65 Grandview Street, Pymble NSW 2073 PH: (02) 8569 2200 FAX: (02) 9983 0582

Location: Cooks Cove Environmental Log: D1BH45

DRILLING INFO.		LITHOLOGY	SAMPL	ING INI		
Depth Method Water	Symbol	Description	Sample ID Type		PID (ppm) 0 09 09 09	Well Construction
0	FI	LL: Gravelly SAND: brown, fine to edium, with angular gravel	D1BH45_0-1.0			
1 - Auger			D1BH45_1.0-1.7			
2-	m cla	LL: Clayey Sand: dark brown, edium, dry with medium plasticity ay, with timber, plastic, ceramic aste	D1BH45_1.7-2.0			
3			D1BH45_2.0-3.0			
5						

Drill Company: SDI

וסטו

Date Commenced:

14/10/15

Drill Model:

Date Completed: 14/10/15

Hole Diameter (mm):

Logged/checked by: EM/JD



ANNEXURE 3: Registered Groundwater Bores within 200 m of Barton Park Boundary

	Groundwater Extraction Bores within 200 m of t														200 m of the			
Hydroid	Hydrocode	Stateborei	Statepipei	Stateterri	Agency	Wcode	Boredepth	Drilleddep	Status	Drilleddat	Hguid	Hgunumber	Nafhgunumb	Ftype	Latitude	Longitude	Easting	Northing
10038509	GW023191.1.1	GW023191	1.1	1	1	11	3.6	3.7	UNK	18000101	-19999999	-9999	-9999	WSUP	-33.943881	151.150091	329041	6242525
10092875	GW100444.1.1	GW100444	1.1	1	1	11	5.49	5.49	UNK	19961122	-19999999	-9999	-9999	HUSE	-33.951144	151.153328	329355	6241725
10038512	GW023194.1.1	GW023194	1.1	1	1	11	4.8	4.9	UNK	19651101	-19999999	-9999	-9999	WSUP	-33.941322	151.151391	329156	6242811
10099338	GW106982.1.1	GW106982	1.1	1	1	11	5	5	UNK	20050207	-19999999	-9999	-9999	RECN	-33.950208	151.153627	329381	6241829
10098809	GW106450.1.1	GW106450	1.1	1	1	11	2	2	ABN	20041008	-19999999	-9999	-9999	HUSE	-33.948403	151.151028	329137	6242025
10100634	GW108295.1.1	GW108295	1.1	1	1	11	8	8	USE	20061101	-19999999	-9999	-9999	HUSE	-33.944391	151.148626	328907	6242466
10101202	GW108870.1.1	GW108870	1.1	1	1	11	5	0	UNK	20080512	-19999999	-9999	-9999	IRAG	-33.946008	151.1507	329102	6242290
10101049	GW108717.1.1	GW108717	1.1	1	1	11	5.183	5.19	USE	20070406	-19999999	-9999	-9999	HUSE	-33.951547	151.1532	329344	6241680
10100773	GW108439.1.1	GW108439	1.1	1	1	11	8	8	UNK	20070105	-19999999	-9999	-9999	HUSE	-33.94428	151.148477	328893	6242478
10103058	GW110735.1.1	GW110735	1.1	1	1	11	8	0	UNK	20060101	-19999999	-9999	-9999	HUSE	-33.943831	151.148945	328935	6242529
10103639	GW111316.1.1	GW111316	1.1	1	1	11	162	162	UNK	20100301	-19999999	-9999	-9999	MON	-33.943811	151.153248	329333	6242538
10103547	GW111224.1.1	GW111224	1.1	1	1	11	6	6	UNK	20100822	-19999999	-9999	-9999	HUSE	-33.951206	151.154419	329456	6241720

Cooks Cove	Site Boundary	y (July 2019)															
Projection	Projecti_1	Coordmetho	Heightdatu	Refelev	Refelevdes	Refelevmet	Tsrefelev	Tsrefelevd	Tsrefelevm	Landelev	Landelevme	Ismultipip	Borelineco	Worksid	Licenceext	Licencee_1	Licenceuse
1	56	MAP	AHD	4.62	NGS	DEM	0	UNK	UNK	4.62	DEM	0		0	0	0	0
1	56	UNK	AHD	2.79	NGS	DEM	0	UNK	UNK	2.79	DEM	0		0	0	0	0
1	56	MAP	AHD	11.12	NGS	DEM	0	UNK	UNK	11.12	DEM	0		0	0	0	0
1	56	UNK	AHD	1.91	NGS	DEM	0	UNK	UNK	1.91	DEM	0		0	0	0	0
1	56	MAP	AHD	5.4	NGS	DEM	0	UNK	UNK	5.4	DEM	0		0	0	0	0
1	56	MAP	AHD	3.53	NGS	DEM	0	UNK	UNK	3.53	DEM	0		0	0	0	0
1	56	UNK	AHD	4.54	NGS	DEM	0	UNK	UNK	4.54	DEM	0		0	0	0	0
1	56	MAP	AHD	3.74	NGS	DEM	0	UNK	UNK	3.74	DEM	0		0	0	0	0
1	56	UNK	AHD	3.82	NGS	DEM	0	UNK	UNK	3.82	DEM	0		0	0	0	0
1	56	UNK	AHD	4.35	NGS	DEM	0	UNK	UNK	4.35	DEM	0		0	0	0	0
1	56	UNK	AHD	4.62	NGS	DEM	4.62	NGS	DEM	4.62	DEM	0		0	0	0	0
1	56	UNK	AHD	2.59	NGS	DEM	0	UNK	UNK	2.59	DEM	0		0	0	0	0


REGISTERED GROUNDWATER BORES




Site boundary

Boundary of residential areaApproximate water mainApproximate sewer mainRegistered groundwater bore









ANNEXURE 4: Edison Geotechnical Borehole Logs



Hole ID.

Sheet:

BHDG101

Hole Depth:

19.43 m 1 of 5

(approx)

Project Name: **Preliminary Geotechnical Investigation**

G20067ROC Project Number:

Barton Park, Banksia NSW Location / Site:

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

Date Started:

17-AUG-20 Ground Level: Easting:

151.153598

RL4.3m

Drill Method:

SFA/NLMC

Date Completed: 17-AUG-20

Client:

Equipment:

Track Mounted Hanjin D&B-8D

Northing: -33.947746

Method	Water Level	Depth (m)	RL (m)	Graphic Log	USCS Symbol	Material Type	Material Description	Consistency / Density	Moisture	Samples / Tests ID No.	SPT	Observations / Comments
SFA	4.5m K	1.0	4.0 		SP		TOPSOIL- Sand, dark brown, fine to medium grained. FILL- Gravelly Sand, dark brown, fine to coarse grained, trace pockets of clay and some cobbles and boulders noted (brick and SS). concrete boulder between 0.7 and 0.9m. FILL- Clayey Sand, brown grey, fine to medium grained, trace fine to coarse gravel (brick, ironstone and SS). concrete boulder between 1.2m and 1.3m. FILL- Sand, black, fine to medium grained, with minor silt and clay and much anthropogenic material (wood, rubber, plastic, wire, glass and metal noted), moderate odour.		m m	ZZ170820-01 1.50-1.95m ZZ170820-02 3.00-3.45m	3 3 N=6	

0	
ĸ	_
∵	
8	
G2006	-
2	
Ü	
'n	
×	
Ч	
=	
늤	
Ш	
S	
Ш	
⋝	-

Damp Slightly Moist Moist Very Moist Wet

Moisture

Additional Comments

Logged By: **Zachary Ziesel** Date: 17-Aug-20 Checked By: Stephen McCormack 24-AUG-20 Date:



Hole ID.

BHDG101

Hole Depth:

19.43 m

Sheet:

2 of 5

Project Name: **Preliminary Geotechnical Investigation**

Geosense

SFA/NLMC

G20067ROC Project Number:

17-AUG-20

Location / Site:

Drilling Company:

Drill Method:

Equipment:

Barton Park, Banksia NSW

MODE Design Corp Pty Ltd Client:

Ground Level: RL4.3m (approx) 151.153598

Date Completed: 17-AUG-20 Easting: Track Mounted Hanjin D&B-8D

Date Started:

Northing: -33.947746

Method Water Level Depth (m) RL (m) Graphic Log USCS Symbol	od (V) Material Description Material Description	Consistency / Density	Moisture	Samples / Tests	SPT	Observations / Comments
	Σ	ŎĞ	Σ			
	FILL- Sand, black, fine to medium grained, with minor silt and clay and much anthropogenic material (wood, rubber, plastic, wire, glass and metal noted), moderate odour. (continued)		m	ZZ170820-03 6.00-6.50m	1 1 2 N=3	
 5.0	SAND- dark grey, fine to medium grained, some silt and clay and shell fragments and occassional pockets of clay/organics.		W			Water table at approcximately 9.5m
Moisture	Additional Comments	<u>'</u>				
D Dry Dp Damp SM Stightly Moist M Moist VM Very Moist W Wet Sd Saturated						
Logged By: Z	achary Ziesel Date: 17-Aug-20	Che	ecked	Bv: Stenk	nen M	cCormack Date: 24-AUG-20

<u>}</u>		
Mo	isture	Additional Comments
D Dp SM M	Dry Damp Slightly Moist Moist	
VM W Sd	Very Moist Wet Saturated	



Hole ID.

Sheet:

BHDG101

Hole Depth:

19.43 m

3 of 5

(approx)

Project Name:

Preliminary Geotechnical Investigation

G20067ROC Project Number:

Barton Park, Banksia NSW Location / Site:

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

Date Started: 17-AUG-20

Client:

RL4.3m

Drill Method:

SFA/NLMC

Date Completed: 17-AUG-20 Easting: 151.153598

Equipment:

Track Mounted Hanjin D&B-8D

Northing: -33.947746

Ground Level:

Method	Water Level	Depth (m)	RL (m)	Graphic Log	USCS Symbol	Material Type	Material Description	Consistency / Density	Moisture	Samples / Tests	0.07	Observations / Comments
Met	Wa	Dec	귒	Gra	nsi	Mat		Der	Moi	ID No.	SPT	
		11.0	-7.0 - - - - -		SP	Alluvium	SAND- dark grey, fine to medium grained, some silt and clay and shell fragments and occassional pockets of clay/organics.(continued)		W	ZZ170820-04 12.00-12.45m	0 0 1 N=1	
SFA		13.0	- - - - - - - -9.0			A						Increase in drilling resistance at 13.0m
		14.0	- - - - - - -10	d			light grey at 13.8m.			ZZ170820-05 13.50-13.95m	3 2 1 N=3	Organic Layer last 100mm of SPT
		15.0	- - -				Sandy CLAY / Clayey SAND- grey and light brown, fine to medium grained.	medium dense to dense	w			Increased drilling torque from 14.7m

$^{\circ}$	
ď	_
9	
G200	_
0	
3	
Ü	
വ	
Õ	
Ч	
_	
ェ	
亩	
B	
ш	
=	_

Wet

Additional Comments Moisture Damp Slightly Moist Moist Very Moist

Logged By: **Zachary Ziesel** Date: 17-Aug-20 Checked By: Stephen McCormack 24-AUG-20 Date:



Hole ID.

BHDG101

Hole Depth:

19.43 m

4 of 5

(approx)

Project Name: **Preliminary Geotechnical Investigation**

G20067ROC Project Number:

Sheet:

Location / Site:

Barton Park, Banksia NSW

Client:

MODE Design Corp Pty Ltd

Ground Level:

Drilling Company:

Geosense

Date Started:

17-AUG-20

Easting:

Drill Method:

SFA/NLMC

Date Completed:

17-AUG-20

151.153598 Northing:

Equipment:

Track Mounted Hanjin D&B-8D

-33.947746

RL4.3m

Method	Water Level	Water Lever		RL (m)	Graphic Log	USCS Symbol	Material Type	Material Description	Consistency / Density	Moisture	Samples / Tests ID No.	SPT	Observations / Comments
Me	×	De M	i	로	Gr	Sn	Ma		0°	Mo	ID No.	011	
SFA		- - - - - - - 16	-	111.0			Residual Soil	Sandy CLAY / Clayey SAND- grey and light brown, fine to medium grained.(continued)	medium dense to dense	w			Drilling resistance increased from 16.2m
		F		12.0				SANDSTONE - grey, fine to coarse grained, Estimated HW/VL strength.				10 /	SPT double bouncing
00.05' 05' 05' 05' 05' 05' 05' 05' 05' 05'		1718191919	.0	14.0			Bedrock	BHDG101 continued as cored hole from 16.5m				-	

G20067ROC	١.
ď	
Ķ	
ö	١.
ŏ	٠.
ä	
00	
О	
_	
I	
m	
ES	
Щ	
>	•

Moisture

Damp Slightly Moist Moist Very Moist Wet

Additional Comments

Logged By: **Zachary Ziesel** Date: 17-Aug-20 Checked By: Stephen McCormack 24-AUG-20 Date:



Hole ID.

Sheet:

BHDG101

Hole Depth:

19.43 m

5 of 5

(approx)

Project Name: **Preliminary Geotechnical Investigation**

G20067ROC Project Number:

17-AUG-20

Barton Park, Banksia NSW Location / Site:

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

17-AUG-20

Client:

Ground Level: RL4.3m Easting: 151.153598

Drill Method:

SFA/NLMC Date Completed:

Northing: Equipment: Track Mounted Hanjin D&B-8D -33.947746

Date Started:

## 19.5 End of Hole at 19.43 m	Method	Water Level	Depth (m)	RL (m)	Graphic Log	Material Type	Material Description	Weathering	Estimated Strength (MPa)	D=diametral M $\overline{\alpha}$ A=axial $\overline{\alpha}$	U.C.S. (Mpa)	RQD %	Core Photo	Defect Spacing (mm)	Defect Description type, inclination, thickness, shape, roughness, coating	eneral	Depth (m)	Casing & Core Lifts
Additional Comments 90 10 10 10 10 10 10 10 10 10 10 10 10 10	9:07:17 AM NMLC Coring	Water Le	17.0 - - - - - - - - - - - - - - - - - - -	12.5 13.0 13.5 13.5 14.0 14.5 15.0 15.0		Material	Continued from non-cored borehole from 16.5m SANDSTONE - grey, fine to coarse grained. clay imbedded and highly weathered from 16.62. SANDSTONE - orange, fine to coarse grained, Fe stained. orange, pink and grey at 17.8m.	DW	i ix	A=0.41 D=0.5 A=0.78 D=0.98	U.C.S. (Core Ph		roughness, coating Specific G — DB — BD, Fe, 1, RG SM, CLAY BD, 0	eneral		19.43
4 	GEE DAVIES CH LOG G20067F	Add	ition	al Co	omm	ents												





Hole ID.

Sheet:

BHDG102

Hole Depth:

3.00 m 1 of 1

(approx)

Project Name: **Preliminary Geotechnical Investigation**

Project Number: **G20067ROC**

Location / Site: Barton Park, Banksia NSW

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

Date Started: 17-AUG-20

Client:

Ground Level: RL4.0m

Drill Method: SFA

Date Completed:

17-AUG-20 Easting:

151.153207 -33.948496

Equipment:

Track Mounted Hanjin D&B-8D

Northing:

Method	Water Level	Depth (m)	RL (m)	Graphic Log	USCS Symbol	Material Type	Material Description	Consistency / Density	Moisture	Observations / Comments
SFA		1.0			SP SP		Surface: Grass TOPSOIL- Silty Sand, dark brown, fine to medium grained. FILL- Sand, brown, fine to mediuim, with some fine to medium gravel and trace silt. increase in gravel at 0.5m. FILL- Sand With Clay, black, fine to medium grained, Much anthropogenic material (plastic, brick and glass noted), moderate odour.	loose very loose to loose	m m	
		3.0 - - - - - - - - - - - - - - - - - - -	-				End of Hole at 3.00m Target Depth Reached			

G20067RO	Ξ
മ	_
$\overline{}$	
9	
9	_
\approx	
22	
Ċ	
, n	
8	
0	
_	
$\overline{}$	
亩	
ш	
ഗ	
ß	
=	_
2	

Dp Damp
SM Slightly Moist
M Moist
VM Very Moist
W Wet

Logged By:

Moisture

Zachary Ziesel

Additional Comments

Date: 17-Aug-20

Checked By:

Stephen McCormack D

Date: 24-AUG-20



Hole ID.

BHDG103

Hole Depth:

Sheet:

3.00 m

1 of 1

(approx)

Project Name:

Preliminary Geotechnical Investigation

G20067ROC Project Number:

Barton Park, Banksia NSW Location / Site:

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

Date Started:

Client:

17-AUG-20 Ground Level:

151.154076

RL4.1m

Drill Method: **SFA** Date Completed:

17-AUG-20

Easting:

Equipment: Track Mounted Hanjin D&B-8D Northing: -33.948127

						<u> </u>			
Method Water Level Depth (m)	(<u>a</u>	(III)	Grapnic Log	USCS Symbol	Material Type	Material Description	Moisture	Samples / Tests ID No.	Observations / Comments
	4.	.0))	SP		Surface: Grass TOPSOIL- Silty Sand, dark brown, fine to medium grained.	m		
- - - - -	-					FILL- Sand, brown, fine to mediuim, trace silt and fine to coarse gravel. Occassional brick and concrete also noted.	m	ZZ170820-G3 (CBR) 0.20-1.20m	
1.0 - - -	3.	٥ 🗴		SP	=			0.20-1.2011	
	- - - - 2.	.0		SP	ii	FILL- Sand With Clay, black, fine to medium grained, Much anthropogenic material (plastic, brick and glass noted), moderate odour.	m		
3.0	- - - - - 1.	0				End of Hole at 3.00m Target Depth Reached			
-	-					g			
4.0 - - - -		.0							
5.0									

0	
œ	_
~	
8	
\approx	-
G 20	
വ	
_	
ര	
0	
ユ	
_	
亩	
ш	
တ	
ш	
⋝	_

Damp Slightly Moist Moist Very Moist Wet

Moisture

Additional Comments

Logged By: **Zachary Ziesel** Date: 17-Aug-20 Checked By: Stephen McCormack Date: 24-AUG-20



Hole ID.

BHDG104

Hole Depth:

Sheet:

3.00 m 1 of 1

(approx)

Project Name: Preliminary

Preliminary Geotechnical Investigation

Project Number: **G20067ROC**

Location / Site: Barton Park, Banksia NSW

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

Date Started: 17-AUG-20

Client:

Ground Level: RL4.4m

Drill Method: SFA

Date Completed: 17-AUG-20

Easting: **151.15344**

Equipment: Track Mounted Hanjin D&B- 8D

Northing: -33.947878

Surface: Grass TOPSOIL- Silty Sand, dark brown, fine to medium grained. FILL- Sand Trace Silt, brown, fine to medium, trace fine to medium gravel. SP FILL- Sand With Clay, black, fine to medium grained, Much anthropogenic material (plastic, fabric, brick, and foam noted), moderate odour. FILL- Sand With Clay, black, fine to medium grained, Much anthropogenic material (fabric, wood and plastic noted), strong odour.
We have a second

ပ	ı
G20067ROC	
ď	
7	
9	
ă	•
Ñ	
ര	
Ō	
90	
_	
ᇤ	
Ш	
ES	
ĭή	
₹	_

Dp Damp
SM Slightly Moist
M Moist
VM Very Moist
W Wet

Logged By:

Moisture

Zachary Ziesel

Additional Comments

Date: 17-Aug-20

Checked By: Stephen McCormack

Date: 24-AUG-20



Hole ID.

Sheet:

BHDG105

Hole Depth:

3.00 m

1 of 1

(approx)

Project Name:

Preliminary Geotechnical Investigation

G20067ROC Project Number:

Barton Park, Banksia NSW Location / Site:

MODE Design Corp Pty Ltd

Drilling Company:

Geosense

Date Started: 17-AUG-20 Ground Level: RL4.7m

Drill Method:

SFA

Date Completed:

17-AUG-20

Easting:

151.153924

Client:

Northing:

Equipment:

Track Mounted Hanjin D&B-8D

-33947411

_											
Method	Water Level	Depth (m)	RL (m)	Graphic Log	USCS Symbol	Material Type	Material Description	Consistency / Density	Moisture	Samples / Tests ID No.	Observations / Comments
							Surface: Gravel road				
Г				XX	GW		FILL- Silty Gravel, grey blue, fine to coarse sand		m		
		-	F				and gravel.	compacted	m	1	
		Ė		\bowtie			FILL- Gravelly Sand, dark brown, fine to coarse sand and gravel.				
		0.5	<u>4</u> .0		SP					ZZ170820-G5 (CBR) 0.20-1.00m	
		-	-	\bowtie							
		Ē	F							_	
SFA		_ _1.5 _	3.0			E	FILL- Sand With Some Clay, black, fine to medium grained, Much anthropogenic material (plastic, rubber and wood noted), moderate odour.		m		
			-	\otimes							
		2.0	F	\bowtie							
		Ė	Ė	\bowtie	SP						
		-	-								
		2.5	_	\bowtie							
		F	2.0	\bowtie							
		Ė	F	\bowtie							
		3.0	-	\bowtie							
Г		-	-				End of Hole at 3.00m				
		L	E				Target Depth Reached				
		3.5	Ē								
		5.5	-								
		-	1.0								
S A			ļ								
9:00:25 AM		4.0	F								
			-								
-6-1-2 -6-1-2		-	F								
<u>.</u>		4.5	Ė								
ווי ווי		F	0.0								
5		F	F								
00/KUC.GPJ GEE.GDJ Z/-8-20		5.0	-								
2	N / - :	ot					Additional Comments				
3	IVIOIS	sture)				Additional Comments				

GEE DAVIES BH LOG G20067ROC.GPJ GEE.GDT 27-8-20 9:06:25 AM

D Dp SM M VM W Sd

Dry Damp Slightly Moist

Moist Very Moist Wet

Logged By: **Zachary Ziesel** Date: 17-Aug-20 Checked By: Stephen McCormack Date: 24-AUG-20



Log Report Legend

MATERIAL SYMBOL



FILL



CONCRETE



ASPHALT



TOPSOIL



ORGANICS



ESTUARINE MUD



CLAY



SAND



SILT



GRAVEL



Sandy CLAY



Clayey SAND



Clayey SILT



Clayey GRAVEL



Silty CLAY



Silty SAND



Sandy SILT



Sandy GRAVEL



Gravelly CLAY



Gravelly SAND



Gravelly SILT



Silty GRAVEL



CLAY & SAND



SAND & CLAY



SILT & CLAY



GRAVEL & CLAY



CLAY & SILT



SAND & SILT



SILT & SAND



GRAVEL & SAND



CLAY & GRAVEL



SAND & GRAVEL



SILT & GRAVEL



GRAVEL & SILT



Sandy Silty CLAY



Clayey Silty SAND



Sandy Clayey SILT



Sandy Clayey GRAVEL



Silty Sandy CLAY



Silty Clayey SAND



Clayey Sandy SILT



Clayey Sandy GRAVEL



Sandy Gravelly CLAY



Clayey Gravelly SAND



Sandy Gravelly SILT



Silty Clayey GRAVEL



Silty Gravelly CLAY







Clayey Gravelly SILT



Clayey Silty GRAVEL



Gravelly Silty CLAY



Gravelly Silty SAND



Gravelly Clayey SILT



Sandy Silty GRAVEL



Gravelly Sandy CLAY



Gravelly Clayey SAND



Gravelly Sandy SILT



Silty Sandy GRAVEL



SANDSTONE



SHALE

GNEISS



GRANITE SHALE /

CLAYSTONE



BASALT MUDSTONE



CLAYSTONE

PORCELLANITE



MUDSTONE / CLAYSTONE



SHALE / SILTSTONE



IRONSTONE

WATER LEVELS



Encountered Water Standing Water

ABBREVIATIONS

Pushtube SFA PWS

Solid Flight Auger Percussion Window Sampler

WELL GRAPHICS



Cuttings



Bentonite



Screen

SHALE /

SANDSTONE



Cave-in

Gravel Pack



Grout





ANNEXURE 5: Laboratory Certificates of Analysis



Geo-Environmental Engineering Pty Ltd 82 Bridge St Lane Cove NSW 2066





NATA Accredited Accreditation Number 1261 Site Number 18217

Accredited for compliance with ISO/IEC 17025 – Testing The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Attention: ALL INVOICES Stephen McCormack

Report738225-SProject nameROCKDALEProject IDROCKDALEReceived DateAug 17, 2020

Client Sample ID Sample Matrix Eurofins Sample No.			ZZ170820-01 Soil S20-Au23553	ZZ170820-04 Soil S20-Au23554	ZZ170820-05 Soil S20-Au23555
Date Sampled			Not Provided ^{I12}	Not Provided ^{I12}	Not Provided ^{I12}
Test/Reference	LOR	Unit			
Chloride	10	mg/kg	36	2000	1100
Conductivity (1:5 aqueous extract at 25°C as rec.)	10	uS/cm	180	1000	580
pH (1:5 Aqueous extract at 25°C as rec.)	0.1	pH Units	7.3	8.3	8.4
Resistivity*	0.5	ohm.m	56	9.9	17
Sulphate (as SO4)	10	mg/kg	81	210	150
% Moisture	1	%	16	27	26



Sample History

Where samples are submitted/analysed over several days, the last date of extraction and analysis is reported.

A recent review of our LIMS has resulted in the correction or clarification of some method identifications. Due to this, some of the method reference information on reports has changed. However, no substantive change has been made to our laboratory methods, and as such there is no change in the validity of current or previous results.

If the date and time of sampling are not provided, the Laboratory will not be responsible for compromised results should testing be performed outside the recommended holding time.

Description	Testing Site	Extracted	Holding Time
Chloride - Method: E045 /E047 Chloride	Sydney	Aug 19, 2020	28 Days
Conductivity (1:5 aqueous extract at 25°C as rec.)	Sydney	Aug 21, 2020	7 Days
- Method: LTM-INO-4030 Conductivity	0.1		7.0
pH (1:5 Aqueous extract at 25°C as rec.) - Method: LTM-GEN-7090 pH in soil by ISE	Sydney	Aug 21, 2020	7 Days
Sulphate (as SO4)	Sydney	Aug 19, 2020	28 Days
- Method: E045 Anions by Ion Chromatography			
% Moisture	Sydney	Aug 17, 2020	14 Days

- Method: LTM-GEN-7080 Moisture

Report Number: 738225-S



Australia

6 Monterey Road
Dandenong South VIC 3175 1
Phone: +613 8564 5000 L
NATA # 1261 Site # 1254 & 14271 Melbourne ABN: 50 005 085 521 web: www.eurofins.com.au email: EnviroSales@eurofins.com

Lane Cove West NSW 2066 Phone: +61 2 9900 8400 NATA # 1261 Site # 18217 Sydney Unit F3, Building F 16 Mars Road

Brisbane 1/21 Smallwood Place Murarine QLD 4172 S Phone : +617 3902 4600 NATA # 1261 Site # 20794

Perth 2/91 Leach Highway Kewdale WA 6105 Phone : +61 8 9251 9600 NATA # 1261 Site # 23736

Newcastle 4/52 Industrial Drive Mayfield East NSW 2304 PO Box 60 Wickham 2293 Phone: +61 2 4968 8448

New Zealand

Christchurch 43 Detroit Drive Rolleston, Christchurch 7675 Phone: 0800 856 450 IANZ # 1290

Auckland 35 O'Rorke Road Penrose, Auckland 1061 Phone: +64 9 526 45 51 IANZ # 1327 Received:

Aug 17, 2020 3:30 PM Priority: Due:

5 Day

ALL INVOICES Stephen

Aug 24, 2020 Contact Name:

738225

Order No.: Report #: Phone:

Geo-Environmental Engineering P/L

Company Name:

Address:

82 Bridge St

Lane Cove NSW 2066

ROCKDALE ROCKDALE

Project Name: Project ID:

Eurofins Analytical Services Manager: Andrew Black

etail
Sa

Moisture Set

Aggressivity Soil Set

Melb	Melbourne Laboratory - NATA Site # 1254 & 14271	ory - NATA Site	# 1254 & 142	71			
Sydr	Sydney Laboratory - NATA Site # 18217	- NATA Site #1	8217			×	
Bris	Brisbane Laboratory - NATA Site # 20794	y - NATA Site#	20794				
Pert	Perth Laboratory - NATA Site # 23736	VATA Site # 237	.36				
New	Newcastle Laboratory	ıry					
Exte	External Laboratory						
Š	Sample ID	Sample Date	Sampling Time	Matrix	LAB ID		
_	ZZ170820-01 Not Provided	Not Provided		Soil	S20-Au23553	×	
7	ZZ170820-04 Not Provided	Not Provided		Soil	S20-Au23554	×	
က	ZZ170820-05 Not Provided	Not Provided		Soil	S20-Au23555	×	
Test	Test Counts					3	

 \times

 $\times \times \times$

က



Internal Quality Control Review and Glossary

General

- Laboratory QC results for Method Blanks, Duplicates, Matrix Spikes, and Laboratory Control Samples follows guidelines delineated in the National Environment Protection (Assessment of Site Contamination) Measure 1999, as amended May 2013 and are included in this QC report where applicable. Additional QC data may be available on request.
- 2. All soil/sediment/solid results are reported on a dry basis, unless otherwise stated.
- All biota/food results are reported on a wet weight basis on the edible portion, unless otherwise stated.
- Actual LORs are matrix dependant. Quoted LORs may be raised where sample extracts are diluted due to interferences.
- 5. Results are uncorrected for matrix spikes or surrogate recoveries except for PFAS compounds
- 6. SVOC analysis on waters are performed on homogenised, unfiltered samples, unless noted otherwise.
- 7. Samples were analysed on an 'as received' basis.
- 8. Information identified on this report with blue colour, indicates data provided by customer, that may have an impact on the results.
- This report replaces any interim results previously issued.

Holding Times

Please refer to 'Sample Preservation and Container Guide' for holding times (QS3001).

For samples received on the last day of holding time, notification of testing requirements should have been received at least 6 hours prior to sample receipt deadlines as stated on the SRA.

If the Laboratory did not receive the information in the required timeframe, and regardless of any other integrity issues, suitably qualified results may still be reported.

Holding times apply from the date of sampling, therefore compliance to these may be outside the laboratory's control.

For VOCs containing vinyl chloride, styrene and 2-chloroethyl vinyl ether the holding time is 7 days however for all other VOCs such as BTEX or C6-10 TRH then the holding time is 14 days.

**NOTE: pH duplicates are reported as a range NOT as RPD

Units

mg/kg: milligrams per kilogram ma/L: milligrams per litre ug/L: micrograms per litre

ppm: Parts per million ppb: Parts per billion %: Percentage

org/100mL: Organisms per 100 millilitres NTU: Nephelometric Turbidity Units MPN/100mL: Most Probable Number of organisms per 100 millilitres

Terms

Dry Where a moisture has been determined on a solid sample the result is expressed on a dry basis.

LOR

SPIKE Addition of the analyte to the sample and reported as percentage recovery. RPD Relative Percent Difference between two Duplicate pieces of analysis.

LCS Laboratory Control Sample - reported as percent recovery. CRM Certified Reference Material - reported as percent recovery.

Method Blank In the case of solid samples these are performed on laboratory certified clean sands and in the case of water samples these are performed on de-ionised water

Surr - Surrogate The addition of a like compound to the analyte target and reported as percentage recovery.

Duplicate A second piece of analysis from the same sample and reported in the same units as the result to show comparison.

USEPA United States Environmental Protection Agency

APHA American Public Health Association TCLP Toxicity Characteristic Leaching Procedure

COC Chain of Custody SRA Sample Receipt Advice

QSM US Department of Defense Quality Systems Manual Version 5.3 CP Client Parent - QC was performed on samples pertaining to this report

NCP Non-Client Parent - QC performed on samples not pertaining to this report, QC is representative of the sequence or batch that client samples were analysed within.

TEQ Toxic Equivalency Quotient

QC - Acceptance Criteria

RPD Duplicates: Global RPD Duplicates Acceptance Criteria is 30% however the following acceptance guidelines are equally applicable:

Results <10 times the LOR: No Limit

Results between 10-20 times the LOR: RPD must lie between 0-50%

Results >20 times the LOR: RPD must lie between 0-30%

Surrogate Recoveries: Recoveries must lie between 20-130% Phenols & 50-150% PFASs

PFAS field samples that contain surrogate recoveries in excess of the QC limit designated in QSM 5.3 where no positive PFAS results have been reported have been reviewed and no data was

WA DWER (n=10): PFBA, PFPeA, PFHxA, PFHpA, PFOA, PFBS, PFHxS, PFOS, 6:2 FTSA, 8:2 FTSA

QC Data General Comments

- 1. Where a result is reported as a less than (<), higher than the nominated LOR, this is due to either matrix interference, extract dilution required due to interferences or contaminant levels within the sample, high moisture content or insufficient sample provided.
- 2. Duplicate data shown within this report that states the word "BATCH" is a Batch Duplicate from outside of your sample batch, but within the laboratory sample batch at a 1:10 ratio. The Parent and Duplicate data shown is not data from your samples.
- 3. Organochlorine Pesticide analysis where reporting LCS data, Toxaphene & Chlordane are not added to the LCS.
- 4. Organochlorine Pesticide analysis where reporting Spike data, Toxaphene is not added to the Spike.
- Total Recoverable Hydrocarbons where reporting Spike & LCS data, a single spike of commercial Hydrocarbon products in the range of C12-C30 is added and it's Total Recovery is reported in the C10-C14 cell of the Report.
- 6. pH and Free Chlorine analysed in the laboratory Analysis on this test must begin within 30 minutes of sampling. Therefore laboratory analysis is unlikely to be completed within holding time. Analysis will begin as soon as possible after sample receipt.
- 7. Recovery Data (Spikes & Surrogates) where chromatographic interference does not allow the determination of Recovery the term "INT" appears against that analyte.
- 8. Polychlorinated Biphenyls are spiked only using Aroclor 1260 in Matrix Spikes and LCS.
- 9. For Matrix Spikes and LCS results a dash " -" in the report means that the specific analyte was not added to the QC sample.
- 10. Duplicate RPDs are calculated from raw analytical data thus it is possible to have two sets of data.

Page 4 of 6



Quality Control Results

Test			Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Method Blank									
Chloride			mg/kg	< 10			10	Pass	
Conductivity (1:5 aqueous extract at 25°C as rec.)			uS/cm	< 10			10	Pass	
Sulphate (as SO4)			mg/kg	< 10			10	Pass	
LCS - % Recovery									
Chloride			%	87			70-130	Pass	
Conductivity (1:5 aqueous extract at 25°C as rec.)			%	90			70-130	Pass	
Sulphate (as SO4)			%	83			70-130	Pass	
Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Spike - % Recovery									
				Result 1					
Chloride	S20-Au24760	NCP	%	88			70-130	Pass	
Sulphate (as SO4)	S20-Au24760	NCP	%	83			70-130	Pass	
Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Duplicate									
				Result 1	Result 2	RPD			
Chloride	S20-Au24760	NCP	mg/kg	19	17	13	30%	Pass	
Conductivity (1:5 aqueous extract at 25°C as rec.)	S20-Au23553	СР	uS/cm	180	190	4.0	30%	Pass	
pH (1:5 Aqueous extract at 25°C as rec.)	S20-Au23553	СР	pH Units	7.3	7.7	Pass	30%	Pass	
Resistivity*	S20-Au23553	CP	ohm.m	56	54	4.0	30%	Pass	
Sulphate (as SO4)	S20-Au24760	NCP	mg/kg	480	470	3.0	30%	Pass	
% Moisture	S20-Au23516	NCP	%	11	11	4.0	30%	Pass	



Comments

Sample Integrity

 Custody Seals Intact (if used)
 N/A

 Attempt to Chill was evident
 No

 Sample correctly preserved
 Yes

 Appropriate sample containers have been used
 Yes

 Sample containers for volatile analysis received with minimal headspace
 Yes

 Samples received within HoldingTime
 N/A

 Some samples have been subcontracted
 No

Qualifier Codes/Comments

Code Description

112 Where sampling date has not been provided, Eurofins | Environment Testing is not able to determine whether analysis has been performed within recommended holding times.

Authorised By

Andrew Black Analytical Services Manager
Gabriele Cordero Senior Analyst-Inorganic (NSW)

Glenn Jackson

General Manager

Final report - this Report replaces any previously issued Report


- Indicates Not Requested
- * Indicates NATA accreditation does not cover the performance of this service

Measurement uncertainty of test data is available on request or please click here.

Eurofins shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Eurofins be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested. Unless indicated otherwise, the tests were performed on the samples as received.

Report Number: 738225-S

POINT LOAD STRENGTH INDEX Project No. G20067ROC 17-Aug-20 Geo-Environmental Engineering Pty Ltd Date: Project: Geotechnical Investigation Tested by: MK Location: 444 - 446 Princes Highway, Rockdale NSW 2216 Data checked: MK Test Locality: MHK Test Machine: GSA Core Size: 52 mm Moisture Bore/TP Depth Rock Type Test D Point Load Failure Type Strength Classification Condition Type (m) (mm) (mm) kN Strength Index (P) Is₍₅₀₎ (MPa) BH-G1 16.57 SANDSTONE 49.0 1.21 0.50 Μ D 52.0 BH-G1 16.57 1.26 0.41 Μ SANDSTONE Α 52.0 50.0 1 2.37 BH-G1 17.47 F D 0.98 М SANDSTONE 52.0 49.0 2.41 F BH-G1 17.47 50.0 0.78 Μ SANDSTONE 52.0 BH-G1 18.55 F D 52.0 2.38 0.95 М SANDSTONE 50.0 18.55 4.08 Н BH-G1 Α 52.0 49.0 1.33 SANDSTONE BH-G1 19.38 SANDSTONE D 52.0 49.0 2.69 1.11 Н BH-G1 F 19.38 52.0 47.0 3.46 1.17 Н SANDSTONE



MOISTURE CONDITION:

Field (F), Saturated (S), Dry (D)


FAILURE TYPE:

- Fracture through fabric of specimen oblique to bedding, not influenced by weak planes.
- 2. Fracture along bedding.
- 3. Fracture influenced by pre-existing joint plane (J), microfracture (M), vein (V), chemical alteration (C).
- 4. Chip or partial fracture.

For specimens tested perpendicular to plane of weakness $D_e^2 = 4WD/\pi$

	CALIFO	ORNIA BEA	RING RATIO	REPORT	-	
Client	Geo-Environmental En	gineering	Source	G3		
Address	82 Bridge Street Lane	Cove 2066	Sample Description Silty SAND		race of Gravel.	
Project	Geotechnical Investigation (G20067ROC)		Report No. S63129-CBR			
Job No.	S20380		Sample No.	No. \$63129		
Test Procedure:	AS 1289.6.1.1	RMS T117	California Bearing Ratio			
	AS 1289.5.1.1 AS 1289.5.2.1	RMS T111 RMS T112	Dry Density / Moisture Conte Dry Density / Moisture Conte			
Sampling:	AS 1289.2.1.1 Sampled by Client - results a	RMS T120	Moisture Content - Oven Dry	1	Method) ate Sampled:	17/08/2020
Preparation:	Prepared in accordance with				ato Gumpiou.	11/00/2020
12						
10				-		
8						
0						
(X) 6						
Load (kN)						
4						
2						
0 0	1 2 3	4 5	6 7 8 Penetration (mm)	9 10	11	12 13
Preparation &	Specification		Density & Moisture		Achieved	Target
Retained on 19	.0mm Sieve (%)	3	Lab Moisture Ratio - LMR	2 (%)	102.5	100.0
Method of Esta	blishing Plasticity Level	Technician Assessment	Lab Density Ratio - LDR ((%)	99.5	100.0
Sample Curing	Time (hrs)	24 hrs	Dry Density - At Compact	ion (t/m³)	1.76	1.77
Compaction Ha		Standard	Dry Density - After Soakir	ng (t/m³)	1.76	-
Surcharge Mas Period of Soak		4.5	Specimen Swell (%) Moisture Content - At Cor	mnaction (%)	14.4	-
	Density - MDD (t/m³)	1.77	Moisture Content - At Compaction (%) Moisture Content - Top 30mm (%)		15.0	-
•	ure Content - OMC (%)	14.1	Moisture Content - Remai	· · ·	14.7	-
Notes:	Accredited for compliance with ISO/	-	40 at a penetratio	Authorised Sign	atory:	
NATA	The results of the tests, calibration this document are traceable to document shall not be reproduced, a	Australian/national standards.	d in This			1/09/2020
*	NATA Accredited Laborato	ry Number: 14874		Chris Lloyd		Date:
MACQUAR GEOŢECH					U7/8 10 I	e Geotechnical Bradford Street ia NSW 2015

DRY DENSITY / OPTIMUM MOISTURE CONTENT REPORT						
Client	Geo-Environmental Engineering	Source	G3			
Address	82 Bridge Street Lane Cove 2066	Sample Description	Silty SAND			
Project	Geotechnical Investigation (G20067ROC)	Report No	S63129-MDD			
Job No	S20380	Sample No	S63129			
Test Procedure: AS1289.5.1.1 Dry Density / Moisture Content Relationship - Standard Compaction AS1289.2.1.1 Moisture Content - Oven Drying Method (Standard Method)						
Sampling:	Sampled by Client - results apply to the sample as rec	eived	Date Sampled: 17/08/2020			
Preparation:	Prepared in accordance with the test method					
	·					



Maximum Dry Density (t/m³)	1.769
Optimum Moisture Content (%)	14.1
Oversize Retained on 19mm sieve (%)	3.1
Oversize Retained on 37.5mm sieve (%)	0.0
Curing Time	29 hrs
Liquid Limit Determination	Technician Assessment



Accredited for compliance with ISO/IEC 17025 - Testing.

The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. This document shall not be reproduced, except in full.

NATA Accredited Laboratory Number: 14874

Authorised Signatory:

age

1/09/2020


Chris Lloyd Date:



Macquarie Geotechnical U7/8 10 Bradford Street Alexandria NSW 2015

	CALIF	ORNIA BEA	RING RATIO	REPORT	-		
Client	Geo-Environmental I	Engineering	Source	G4-G5			
Address	82 Bridge Street Lan	e Cove 2066	Sample Description	Silty SAND with	Silty SAND with Gravel.		
Project	Geotechnical Investi	gation (G20067ROC)	Report No. S63130-CBR				
Job No.	S20380		Sample No. S63130				
Test Procedure	_	RMS T117	California Bearing Ratio Dry Density / Moisture Content Relationship - Standard Compaction				
	AS 1289.5.1.1 AS 1289.5.2.1	RMS T111 RMS T112	Dry Density / Moisture Conte Dry Density / Moisture Conte				
	AS 1289.2.1.1	RMS T120	Moisture Content - Oven Dry	1		.=	
Sampling: Preparation:	Prepared in accordance w	s apply to the sample as rec	eived	Di	ate Sampled:	17/08/2020	
ттерагацоп.	1 Toparea III accordance W	iai iio tost monod					
16							
14							
12				0			
10							
$\widehat{\mathbf{z}}$							
Load (kN)							
ە 6							
4							
2							
0							
0	1 2 3	4 5	6 7 8 Penetration (mm)	9 10	11	12 13	
Preparation 8	Specification		Density & Moisture		Achieved	Target	
Retained on 1	9.0mm Sieve (%)	4	Lab Moisture Ratio - LMR	. (%)	97.5	100.0	
Method of Est	ablishing Plasticity Level	Technician Assessment	Lab Density Ratio - LDR (%)	100.5	100.0	
Sample Curing	Time (hrs)	24 hrs	Dry Density - At Compact	ion (t/m³)	1.88	1.87	
Compaction H	ammer Used	Standard	Dry Density - After Soakir	ng (t/m³)	1.88		
Surcharge Ma	ss Applied (kg)	4.5	Specimen Swell (%)		0.0	1	
Period of Soal	king (Days)	4	Moisture Content - At Compaction (%)		11.6	1	
Maximum Dry	Density - MDD (t/m³)	1.87	Moisture Content - Top 30	Omm (%)	12.7	1	
Optimum Mois	sture Content - OMC (%)	11.9	Moisture Content - Remai	inder (%)	12.1	1	
Notes:	Accredited for compliance with IS	ions and/or measurements include	35 at a penetratio	Authorised Sign	atory:	1/09/2020	
NAIA	this document are traceable t document shall not be reproduce	o Australian/national standards.	Γhis			., 55, 2020	
	NATA Accredited Labora	tory Number: 14874		Chris Lloyd		Date:	
MACQUAR GEOŢEC					U7/8 10 I	ie Geotechnical Bradford Street ia NSW 2015	

DRY DENSITY / OPTIMUM MOISTURE CONTENT REPORT						
Client	Geo-Environmental Engineering	Source	G4-G5			
Address	82 Bridge Street Lane Cove 2066	Sample Description	Silty Gravelly SAND			
Project	Geotechnical Investigation (G20067ROC)	Report No	S63130-I	MDD		
Job No	S20380	Sample No	S63130			
Test Procedure: AS1289.5.1.1 Dry Density / Moisture Content Relationship - Standard Compaction AS1289.2.1.1 Moisture Content - Oven Drying Method (Standard Method)						
Sampling:	Sampled by Client - results apply to the sample as re	eceived		Date Sampled:	17/08/2020	
Preparation:	Prepared in accordance with the test method					



Maximum Dry Density (t/m³)	1.870
Optimum Moisture Content (%)	11.9
Oversize Retained on 19mm sieve (%)	3.8
Oversize Retained on 37.5mm sieve (%)	0.0
Curing Time	28 hrs
Liquid Limit Determination	Technician Assessment



Accredited for compliance with ISO/IEC 17025 - Testing.

The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. This document shall not be reproduced, except in full.

NATA Accredited Laboratory Number: 14874

Authorised Signatory:

Chris Lloyd

1/09/2020

Date:



Macquarie Geotechnical U7/8 10 Bradford Street Alexandria NSW 2015